

4-031972

P-23

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-179-20,153 - 02-00

SE NW /4 SEC. 35, 08 S, 27 W
3300 feet from S section line
3300 feet from E section line

Operator license# 5363

Lease Jerome well # 1

Operator: Berexco, Inc.

County Sheridan

Address: P.O. Box 723
Hays, Kansas 67601

Well total depth 4030 feet ^{130.98}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 7 1/2 Inch @ 252 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Berexco, Inc. License# 5363

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 23 Month: August Year: 94

Plugging proposal received from: Paul

Company: Berexco, Inc. Phone: 913-628-6101

Were: Order 320 sxs. 60/40 pozmix - 10% gel - 500# hulls.
Allied Cement Company.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 9:50A.M., Day: 23, Month: August, Year: 94

Actual plugging report: 7" set @ 252' w/140 sxs. 4 1/2" set @ 4028' w/100 sxs. Shot @ 1444'. Squeezed @ 1865' w/125 sxs. - 1937' w/17 sxs. 1940' w/100 sxs. - 2022' - 2132' w/17 sxs. - 2400' w/100 sxs. - 2465' w/125 sxs. - 3000' w/100 sxs. - 3076' w/20 sxs. Prod. perf. 3817'-3956'. PBT 3980'. Squeezed 4 1/2" w/200 sxs. cement blend w/450# hulls mixed in to Max. P.S.I. 1000#. Close in P.S.I. 600#. Squeezed 8 5/8" w/50 sxs. cement w/50# hulls mixed in to Max. P.S.I. 200#. Close in P.S.I. 200#. Plug complete.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES, CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING X. Elevation: GL

I did observe the plugging.

INVOICED

Carl Goodrow SEP 09 1994

DATE 9-12-94

HO

(agent)

Form CP-2/3

CONSERVATION DIVISION WICHITA, KANSAS

INV. NO. 41212