

4 050104

6-26

73R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-179-20,179-00-00

NE SW NW, SEC. 35, T. 8 S, R 27 W ~~EX~~

3630 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Lease Name Jerome Well # 3

Operator: Berexco Inc.

County Sheridan 131.30

Name & Address P.O. Box 723

Well Total Depth 4040 feet

Hays, Kansas 67601

Conductor Pipe: Size \_\_\_\_\_ feet

913-628-6101

Surface Casing: Size 8 5/8 feet 249.25 <sup>KCC</sup> ZAP

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor B J. Services Inc. License Number \_\_\_\_\_

Address \_\_\_\_\_

Company to plug at: Hour: P.M. Day: 26 Month: 6 Year: 19 91

Plugging proposal received from Ted Crawford

(company name) Berexco Inc. (phone) \_\_\_\_\_

were: Order 400 sks. 65/35 poz. 8% gel.

RECEIVED  
STATE CORPORATION COMMISSION  
1111 11 1991  
CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by Marvin Miller  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 7:30 P.M. Day: 26 Month: 6 Year: 19 91

ACTUAL PLUGGING REPORT Mercury Wire Line perforated anhydrite @ 2290' and Dakota

@ 1440'. Ran tubing to 3344 pumped 50 sks. 65/35 poz. 8% gel down tubing.

Pulled tubing to 2229' pumped 50 sks. cement down tubing. Pulled tubing to

1114' circulated cement to surface with 50 sks. cement. Pulled rest of tubing

tied onto 5 1/2 casing and squeezed with 130 sks. cement @ 250 P.S.I. and 150 P.S.I.

shut-in. Tied onto backside, squeezed with 120 sks. cement @ 100 P.S.I. and 50 P.S.I. shut in.

INVOICED

Remarks: (If additional description is necessary, use BACK of this form.)

DATE (did / observe this plugging. 7-22-91)

INV. NO. 32349

*Jib.S.*

Signed Marvin Miller  
(TECHNICIAN)