

4-031974

8-23

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-179-20,231 - 00 00

SW NW NW /4 SEC. 35, 08 S, 27 W  
4290 feet from S section line  
4950 feet from E section line

Operator license# 5363 Lease Jerome well # 6

Operator: Berexco, Inc. County Sheridan

Address: P.O. Box 723 Well total depth 4023 feet  
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 265 feet

130.75

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Berexco, Inc. License# 5363

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 23 Month: August Year: 94

Plugging proposal received from: Paul

Company: Berexco, Inc. Phone: 913-628-6101

Were: Order 320 sxs. 60/40 pozmix - 10% gel - 500# hulls.  
Allied Cement Company.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 2:00P.M., Day: 23, Month: August, Year: 94

Actual plugging report: 8 5/8" set @ 265' w/200 sxs. 5 1/2" set @ 4022'  
w/200 sxs. Prod. perms. 3848' - 3976'. PBD 3999'. Squeezed 2050'  
w/150 sxs. Shot at 1450'. Squeezed 8 5/8" w/50 sxs. cement blend w/50#  
hulls to Max. P.S.I. 200#. Close in P.S.I. 100#. Ran tubing to 2100'  
displaced 80 sxs. cement blend. Pulled tubing to 1000' cwc w/60 sxs.  
cement blend. Pulled tubing. Squeezed 5 1/2" with total 270 sxs. cement  
blend w/450# hulls mixed in to Max. P.S.I. 500#. Close in P.S.I. 100#.  
Plug complete.

Remarks: Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO  
Bottom plug(in place): YES, CALC X, NO Dakota plug: YES X, NO  
Plugged through TUBING, CASING X. Elevation: GL

I did not observe the plugging.

INVOICED

Carl Goodrow SEP 09 1994

DATE 9-12-94

(agent)

INV. NO. 41214

RECEIVED STATE CORPORATION COMMISSION 9/9/94