

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-20929-00-01
Spot: SESWNE Sec/Twnshp/Rge: 33-8S-28W
2970 feet from S Section Line, 1815 feet from E Section Line
Lease/Unit Name: SCHAMBERGER Well Number: 1
County: SHERIDAN Total Vertical Depth: 4051 feet

Operator License No.: 6931
Op Name: BOWMAN OIL COMPANY
Address: 805 CODELL RD.
CODELL, KS 67663

Conductor Pipe: Size _____ feet: 8/31.66
Surface Casing: Size 8.625 feet: 227 170 SX CMT
Production: Size 4.5 feet: 4051 200 SX CMT
Liner: Size _____ feet: _____

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/01/2002 9:00 AM
Plug Co. License No.: 6931 Plug Co. Name: BOWMAN OIL COMPANY
Proposal Rcvd. from: DON BOWMAN Company: BOWMAN OIL COMPANY Phone: (785) 434-7202

Proposed Plugging Method: D.V. at 2380' circulate with 700 sxs cement.
Ordered 175 sxs 60/40 pozmix - 400# hulls - 9 sxs gel.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/01/2002 12:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Squeezed 4 1/2" casing with 25 sxs cement, plus 300# hulls, followed with 9 sxs gel, followed with 125 sxs cement.
Max. P.S.I. 800#.
8 5/8" S.P. - pressure up to 500#.

RECEIVED

JUN 26 2002

KCC WICHITA

6-26-2002

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Dennis L. Hamel
(TECHNICIAN)

INVOICED

DATE 6-27-02

INV. NO. 2002062014

Form CP-2/3

JUN 17 2002

STATE: KANSAS COUNTY: SHERIDAN REISSUE OWWO 33-8S-28W
FIELD: FREDA NORTH 1/2 MI N PROD (LANSING) SE SW NE
OPER: BOWMAN OIL 2970 FSL 1815 FEL SEC
WELL: 1 SCHAMBERGER WELL CLASS: WOE ELEV: 2716 KB
API: 15-179-20929-0001 STATUS: OIL-WO 2711 GR
SPUD: 09/26/91 COMP: 12/28/91
DTD: 4092 LTD: FTD: LANSING PBTD: 3950

LOC: 2 1/2 MI S HOXIE, KS

IP: COMP 12/28/91, IPP 10 BO, 20 BWPD PROD ZONE- TOPEKA 3746-3748
NO CORES OR DSTS (TOPEKA EXTENSION)

CSGS: 4 1/2 @ 4051 W/200 SX; DRLG COMP 09/28/91

OWWO: OWWO: OLD INFO: FORMERLY VIKING RESOURCES # 1 SHAW "A". SPUD 08/06/88.
8 5/8 @ 227 W/170 SX LOG TOPS: TOPEKA 3594, HEEBNER 3806, TORONTO 3833,
LANSING 3846. OTD 4092. COMP 08/14/88. D&A. NEW INFO: TO RETEST.

PERFS: PERF (KANSAS CITY) 3974-3978 W/2 PF, ACID W/250 GALS, , BRPG 3950
PRODUCING INTERVAL: PERF (TOPEKA) 3746-3748 W/2 PF,

OPER ADD: BOX 17, CODELL, KS, 67630 PHONE (914) 434-2304;

CONTR: EMPHASIS OIL OPRTN

WELL ID CHANGES: ELEV CHGD FROM 2716 GR;

REISSUED TO CORRECT ELEV, SPUD DATE, IP, ADD TD REACHED, CSG, PROD TEST
REPLACES CARD ISSUED 1/24/92

COPYRIGHT 1993 PETROLEUM INFORMATION CORPORATION

DATE 06/11/93 CARD #00081-KS

11/10/93