

10-22

4-071071

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-179-21,067-00-00

C NE SE /4 SEC. 36, 08 S, 28 W
2310 feet from S section line
660 feet from E section line

Operator license# 3736 Lease Morgan well # 1

Operator: RLT Investment County Sheridan

Address: Box 63 Well total depth 4000 feet ^{130,00}
Morland, Kansas 67650 Conductor Pipe: 0 inch @ 0 feet
Leon Pfeifer Surface pipe 8 5/8 Inch @ 207 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Allied Cement - Mallard Drilling License# -

Address: Oakley, Kansas - McPherson, Kansas

Company to plug at: Hour: A.M. Day: 22 Month: October Year: 93

Plugging proposal received from: Pam & Arme Hess

Company: Mallard Drilling - J.V. Inc. Phone:

Were: 8 5/8" - 207' S.P. cwc. w/140 sxs. 60/40 pozmix - 2% gel - 3% c.c. By Allied. Elv. 2623' - Anhy. 2250' - K.C. Well - No circulation problems - Mud condition 45 vis. - 9.7 wt. Proposal 200 sxs. 60/40 pozmix - 6% gel - 1 sx. F.C. Circulate - Spot with drill stem - Heavy mud between all plugs. 25 sxs. @ 2260' - 100 sxs. with 1 sx. F.C. @ 1420' - 40 sxs. @ 260' - 10 sxs. @ 40'. 15 sxs. in rathole (circulate) 10 sxs. in Mousehole (circulate)

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 6:00A.M., Day: 22, Month: October, Year: 93

Actual plugging report: Mallard ordered 200 sxs. 60/40 pozmix - 6% gel - 1 sx. F.C. Spotted and displaced all cement through drill pipe - circulated hole - heavy mud between all plugs.

1st. plug @ 2260' w/25 sxs. cement.

2nd. plug @ 1420' w/100 sxs. cement w/1 sx. F.C.

3rd. plug @ 260' w/40 sxs. cement.

4th. plug @ 40' w/10 sxs. cement.

15 sxs. in rathole (circulate) - 10 sxs. in mousehole (circulate)

Remarks: Cemented by Allied Cement.

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES NO X

Bottom plug(in place): YES , CALC , NO X Dakota plug: YES X, NO

Plugged through TUBING , CASING . Elevation: GL

I did not observe the plugging.

Marion J. Schmidt
(agent)

RECEIVED
NOV 05 1993
115-93
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 11-8-93

INV. NO. 39168

10-22