

4 060080

4-21

214
P

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-179-20,959-0000
SE SW SE, SEC. 25, T 8 S, R 30 W XX

TECHNICIAN'S PLUGGING REPORT

330 feet from S section line
1650 feet from E section line

Operator License # 4767

Lease Name Ottley Well # 1

Operator: Ritchie Exploration, Inc.
Name & Address 125 N. Market, Suite 1000
Wichita, KS 67202

County Sheridan 137.67

Well Total Depth 4236 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 270

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XXXXX

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drlg. License Number 6033

Address Wichita, KS

Company to plug at: Hour: 1:30PM Day: 21 Month: April Year: 19 90

Plugging proposal received from Lloyd Delett

(company name) Murfin Drlg. (phone) 316-267-3241

were: Order 200 sxs. 60/40 pos 6%gel 1/4# floccel per sx.

Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by Herb Deines
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XXXXXXXX

Operations Completed: Hour: 1:30PM Day: 21 Month: April Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2540' with 25 sxs. Anhydrite 2533-2557'

2nd plug at 1675' with 100 sxs. Dakota 1373-1673'

3rd plug at 320' with 40 sxs. Surface pipe to 270'

4th plug at 40' with 10 sxs. wiper plug at 40'

rathole with 15 sxs. mousehole with 10 sxs.

Remarks: Allied Cementing
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-9-90

INV. NO. 28084

J.D.S.

Signed [Signature]
(TECHNICIAN)

Herb Deines