

4 060151

142R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-179-20.987-00-00
SE NE SW, SEC. 29, T 8 S, R 30 W/E
1650 feet from S section line
2870 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9860

Lease Name Baalman Well # 1

Operator: Castle Resources

County Sheridan 139.26

Name & Address Rt. 1 Box 90

Well Total Depth 4285 feet

Hays, KS 67601

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 289

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XXXXXX

Other well as hereinafter indicated _____

Plugging Contractor Emphasis Oil Operations License Number 8241

Address Russell, KS 67665

Company to plug at: Hour: 5:00AM Day: 23 Month: January Year: 19 91

Plugging proposal received from John Collins

(company name) Emphasis Oil Operations (phone) _____

were: Order 190 sxs. 60/40pos 6%gel 1/4# floccel per sx.

Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by Herb Deines
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XXXXXX

Operations Completed: Hour: 5:00AM Day: 23 Month: January Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2575' with 25 sxs. Anhydrite 2552-2591'

2nd plug at 1730' with 100 sxs. Dakota 1428-1728'

3rd plug at 340' with 40 sxs. Surface pipe to 289'

4th plug at 40' with 10 sxs.

rathole with 15 sxs.

RECEIVED
STATE CORPORATION COMMISSION
01-28-1991
JAN 28 1991

Remarks: Halliburton Cementing

(If additional description is necessary, use BACK of this form.)

INVOICED

I ~~XXXXXX~~ did not observe this plugging.

DATE 2-11-91

INV. NO. 30644

J.H.S.

Signed Herb Deines
(TECHNICIAN)

Herb Deines