

4-071147

R 10-5

API Number: 15-193-20,637-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

SW SW SW /4 SEC. 22, 08 S, 32 W
330 feet from S section line
4950 feet from E section line

Operator license# 4629

Lease: Smith Well # 1-22

Operator: Brito Oil Company, Inc.

County: Thomas

Address: 120 S. Market - #300
Wichita, Kansas 67202
Paul F. Brito

Well total depth 4715 153.24 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 313 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Abercrombie Drilling - Allied Cementing License# 30684

Address: Wichita, Kansas 67202 - Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 5 Month: October Year: 1995

Plugging proposal received from: Tony Martin

Company: Abercrombie Drilling Phone: 316-263-8787

Were: 8 5/8" - 313' S.P. cwc. w/190 sxs 60/40 pozmix - 2% gel - 3% c.c. By Allied Cementing. Elv. 3100' - Anhy. 2692' - Miss. well - No circulation problems. Mud condition 50 vis - 9.4 wt. - 9.6 water loss - 1500 ppm. cl. at 4400'. Proposal 190 sxs 60/40 pozmix - 6% gel - 1/4# flocele per sack. Spot and displace all cement through drill stem. Heavy mud between all plugs. 25 sxs at 2700' - 100 sxs at 1900' - 40 sxs at 360' - 10 sxs at 40'. 15 sxs in rathole (circulate).

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 2:00 P.M. Day: 5 Month: October Year: 1995

Actual plugging report: Abercrombie ordered 190 sxs 60/40 pozmix - 6% gel - 1/4# flocele per sack - spotted and displaced all cement through drill stem with heavy mud between all plugs.

1st. Plug at 2700' w/25 sxs cement.

2nd. Plug at 1900' w/100 sxs cement.

3rd. Plug at 360' w/40 sxs cement.

4th. Plug at 40' w/10 sxs cement.

15 sxs in Rathole (circulated)

RECEIVED
STATE CORPORATION COMMISSION

OCT 13 1995

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Cemented by Allied Cementing - Russell, Kansas 67665

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO

Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING X, CASING Elevation: 3100 GL

I did not observe the plugging.

Marion J. Schmidt
(agent)

Form CP-2/3

INVOICED
DATE 10-17-95
INV. NO. 43804