

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-193-20214-00-00
Spot: S2SESE Sec/Twnshp/Rge: 29-8S-36W
330 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: FULWIDER Well Number: 1
County: THOMAS Total Vertical Depth: 4770 feet

Operator License No.: 31514
Op Name: THOROUGHBRED ASSOCIATES L.L.C.
Address: 8100 E. 22ND ST. - BUILDING 600
WICHITA, KS 67226

Production Casing Size: 2.875 feet: 856 160 SX CMT
Surface Casing Size: 8.625 feet: 285 200 SXX CMT **#155⁰³**

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/23/2003 5:00 PM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: CINDA SARIA Company: THOROUGHBRED ASSOCIATES LL Phone: (316) 685-1512

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel.
Top down plug through 2 7/8" production casing.
Connected to 8 5/8" surface casing - squeeze with cement.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 07/23/2003 5:35 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

T.D. 4770'. PBTD 856'. Perfs 762' - 772'.
8 5/8" S.P. set at 285' w/200 sxs. 2 7/8" production casing set at 856' w/160 sxs.
Connected to 2 7/8" production casing. Pumped 100 sxs cement with 200# hulls.
Max. P.S.I. 550#. S.I.P. 350#.
Connected to 8 5/8" surface casing. Pumped .25 bbls water.
Max. P.S.I. 500#.

RECEIVED
JUL 30 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

INVOICED

DATE 7-30-03

INV. NO. 2004060276

Form CP-2/3

JUL 24 2003

ABRAXAS, PETROLEUM CORP
 P.O. BOX 17485 #1 FULWIDER 29-8-36W
 SAN ANTONIO, TX 78217 C S/2 SE SE
 CONTR RAINIS & WILLIAMSON CITY THOMAS

GEOL _____ FIELD STUDER EXT (1/8 NW)

E 3407 KB C 10/22/80 CARD ISSUED 1/8/81 IP SIGW
 3400 GL 762-772
 API 15-193-20,214 NEW PAY

+	+	+
+	+	+
+	+	+

LOG	TOPS	DEPTH	DATUM
ANH		2902	+ 505
HEEB		4165	- 758
LANS		4210	- 803
B KC		4488	-1081
MARM		4532	-1125
PAW		4614	-1207
FT SC		4654	-1247
CHER		4674	-1267
PBTD		856	+2551
RTD		4770	-1363

8-5/8" 285/200sx, 2-7/8" 856/160sx
 NO BST'S REPORTED
 MICT - CO, PBTD 856', PF 40/762-772,
 FRAC 7200 GAL GEL WTR & 10,000# SD,
 SIGW

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

KCC
 JUL 29 2003
HAYS, KS