

4-032118

15-181-00032-0000

8
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 1939

12-16

C SE NW /4 SEC. 27 , 08 , 39 W
3300 feet from S section line
3300 feet from E section line

Operator license# -

Lease: Wilcox Well # 1

Operator: Kansas Corporation Commission

County: Sherman

Address: 2301 E. 13th Street
Hays, Kansas 67601
State Of Kansas Fee Fund

Well total depth 1100 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ Unknown feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: State Of Kansas License# -

Address: 2301 E. 13th Street - Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 16 Month: December Year: 1995

Plugging proposal received from: Carl Goodrow and Herb Deines

Company: State of Kansas - District #4 - Hays, Ks Phone: 913-628-1200

Were: Order 125 sxs 60/40 pozmix - 10% gel - 500# hulls. Allied Cement Company.
Hire Murfin Drilling, Inc. - derrick - mud pump and swivel - work string and water truck.
Hire Allied Cement Company for plugging material and placement.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 9:45 A.M., Day: 16, Month: December, Year: 1995

Actual plugging report: 8 5/8" set at 10'. 7" set at 700'. 6" set at 645' in 1939 - no other information is available. Rig up and run 7 7/8" bit stacked out at 10'. Changed bit to 5 1/4" bit. Ran bit to 220'. Hit a wooden bridge - drilled out wood and hit sand - drilled and circulated sand to 520'. Hit wood and shale bridge - drilled out bridge and drilled in hard shale to 600'. Circulated hole clean. Pulled drill collars and pipe, ran back in with plugging string to 600' - stage cement to surface, tied onto 8 5/8" - welded on collar and squeezed with total of 125 sxs cement blend with 500# hulls added in to Max. P.S.I.

Remarks:

Condition of casing(in hole): GOOD BAD DEC 16 1995 12-26-95 Any plug: YES NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES NO

Plugged through TUBING , CASING . Elevation: GL

I did[] / did not[] observe the plugging.

Carl Goodrow
(agent)

OKHD.