

4-060928

API Number: 15-141-20,316 -00-00

7-16

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

SW SE SW /4 SEC. 34, 09 S, 12 W  
330 feet from S section line  
3630 feet from E section line

Operator license# 3956

Lease: Brant Well # 3

Operator: Brungardt Oil & Leasing

County: Osborne

Address: P.O. Box 871  
Russell, Kansas 67665

Well total depth 3450 112.12 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 954 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Shields Oil Producers License# 5184

Address: Russell, Kansas 67665

Company to plug at: Hour: 5:00 A.M. Day: 16 Month: July Year: 1996

Plugging proposal received from: Burt Beery

Company: Shields Oil Producers Phone: 913-483-4975

Were: Order 155 sxs 60/40 posmix - 6% gel with 1/4# floseal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

RECEIVED  
KANSAS CORPORATION COMMISSION

JUL 18 1996

CONSERVATION DIVISION  
WICHITA, KS

7-18-96

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All [ ], Part [ ], None [ X ]

Completed: Hour: 7:00 A.M. Day: 16 Month: July Year: 1996

Actual plugging report:  
1st. Plug at 955' w/40 sxs. - Anhydrite 944' - 977'.  
2nd. Plug at 725' w/80 sxs. - Surface pipe to 954'.  
3rd. Plug at 40' w/10 sxs. - Dakota 479' - 729'.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

Remarks: Halliburton Cementing.  
Condition of casing(in hole): GOOD X BAD  
Bottom plug(in place): YES, CALC, NO X Dakota plug: YES X, NO  
Plugged through TUBING, CASING. Elevation: 1879 GL

Plugging agent [ ] did not [ X ] observe the plugging.

*[Signature]*  
(agent)

Form CP-2/3

INVOICED  
DATE 7-24-96  
INV. NO. 46082