

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

**WELL PLUGGING APPLICATION FORM**  
(File One Copy)

API NUMBER 15-179-20,970-00-00 (of this well).  
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Parrish Corp. OPERATOR'S LICENSE NO. 5228

ADDRESS 100 S. Market, Suite 200 Wichita, KS 67202 PHONE # (316) 263-8726

LEASE (FARM) Pratt #1 WELL NO. #1 WELL LOCATION C.S/2 SW COUNTY Sheridan

SEC. 29 TWP. 8S RGE. 26 (E) or  (W) TOTAL DEPTH 4000' PLUG BACK TD \_\_\_\_\_

**Check One:**

OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ D & A  SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8" SET AT 259' CEMENTED WITH 60-40 pozmix SACKS 180

CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS \_\_\_\_\_

PERFORATED AT \_\_\_\_\_

CONDITION OF WELL: GOOD  POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

PROPOSED METHOD OF PLUGGING Fill w/heavy mud, set 1st plug @ 2240' w/25 sx; 2nd plug @ 1375' w/100 sx; 3rd plug @ 300' w/40 sx; 4th plug @ 40' wiper plug w/10 sx; 15 sx rathole, 10 sx mousehole, 200 sx 60-40 pozmix, 6% gel 1/4# floccel per sx.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? \_\_\_\_\_ IS ACO-1 FILED? No  
(If not explain.) Sent to Operator to complete

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 9-8-90 7:00 a.m.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Bill Craig, Sr. PHONE # (913) 674-2876

ADDRESS Box 297 Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

RECEIVED  
STATE CORPORATION COMMISSION

09-28-1990 SIGNED:  
SEP 28 1990

Jack K. Wharton  
(Operator or Agent)

CONSERVATION DIVISION DATE: Sept 27, 1990  
Wichita, Kansas