

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 205-27232-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 07/12/07

Well Operator: Cherokee Wells, LLC KCC License #: 33539
(Owner / Company Name) (Operator's)

Address: P. O. Box 296 City: Fredonia

State: Kansas Zip Code: 66736 Contact Phone: (620) 378 - 3650

Lease: Pierpoint Farms Well #: A-7 Sec. 4 Twp. 28 S. R. 15 East West

- S/2 - SE - SE Spot Location / QQQQ County: Wilson

330 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

660 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well

SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: N/A Set at: N/A Cemented with: N/A Sacks

Surface Casing Size: 8.625" Set at: 50' Cemented with: 75 sx of Class A Portland Sacks

Production Casing Size: N/A Set at: N/A Cemented with: N/A Sacks

List (ALL) Perforations and Bridgeplug Sets: None

Elevation: 840.6 (G.L. / K.B.) T.D.: 655' PBDT: N/A Anhydrite Depth: N/A
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Well is 6.75" Open Hole - Surface casing did not seal and leaked around pipe. Cement squeeze was attempted - no success. Clean out w/6.75" bit to TD of 655'. Pump cement thru drill stem from TD to Surface.

Let cement cure for 72 Hrs then cut off casing 3' below surface.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? Form ACO-1 is attached - Well was not open hole logged other than Gamma-Ray / Neutron from just below surface casing to verify depth of casing.

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Jeff Morris

Phone: (620) 212 - 4089

Address: P.O. Box 296 City / State: Fredonia, Kansas 66736

Plugging Contractor: Well Refined Drilling KCC License #: 33072
(Company Name) (Contractor's)

Address: 4230 Douglas Rd, Thayer, Kansas Phone: (620) 839 - 5581

Proposed Date and Hour of Plugging (if known?): Wednesday, August 08, 2007 @ approx. 10:00 AM

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 8/1/07 Authorized Operator / Agent: Shannon Shink
(Signature)

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 02 2007

CONSERVATION DIVISION
WICHITA, KS



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

CHEROKEE WELLS LLC
4916 CAMP BOWIE BLVD., SUITE 204
FORT WORTH, TX 76107

August 08, 2007

Re: PIERPOINT FARMS #A-7
API 15-205-27232-00-00
4-28S-15E, 330 FSL 660 FEL
WILSON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after February 4, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #3
1500 W. 7th
Chanute, KS 67220
(620) 432-2300