

15-065-19101-00-01
11-18-54

6030472

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-19101-00-01
SWSW NE, SEC. 17, T. 8 S, R. 25 (W)
3300 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5242

Lease Name Hadden-Davis Well Unit - 106

Operator: Petroleum Management Inc.

County Graham 126.07

Name & Address 400 N Woodlawn Ste. 201

Well Total Depth 3879 feet

Wichita, Kansas

Conductor Pipe: Size _____ feet

67208

Surface Casing: Size 10 3/4 feet 513

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton License Number _____

Address Oberlin Kansas

Company to plug at: Hour: AM Day: 12 Month: 6 Year: 19 85

Plugging proposal received from Wayne Fuzzell

(company name) P.M.I. (phone) _____

were: 10 3/4 in @ 513' w/ 230 af. 7" in @ 3874 w/ 100 af. Top of 3687

PBYD 3860 Order 300 af 50/50 gel 6 bags 3 bu. 40 af gel. 4 ash hulls. 7" WP.

Halliburton am. hauler and wellrock water trucks.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 12:50 PM Day: 12 Month: 6 Year: 19 85

ACTUAL PLUGGING REPORT Pump down 10 3/4 annulet with 120 af Cem. mix.

Close in 150th Pump down 7" with 60 af Cem. mix. 3 af hulls. - 35 af

gel. 1 af hulls. 50 af Cem. mix, 5 af gel. 7" WP. 70 af Cem. mix. Max PSE.

200th bled off removed Plug Container. Plug Complete

Backside and 7" communicated squeezed both together.

JUN 24 1985 6/24/85

Remarks: _____
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED
Observe this plugging.

6-26-85

Signed Carl Goodrow
(TECHNICIAN)

25
6-21-85
MJK

DATE 8740
INV. NO. _____