

4-041993

10-26

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-065-20,200 - 08-00

C NW SW /4 SEC. 25, 08 S, 25 W  
1980 feet from S section line  
4620 feet from E section line

Operator license# 31566

Lease: L&R Schamberger Well # 1

Operator: Benchmark Oil & Gas

County: Graham 130.98

Address: 1515 Arapahoe Street - #580  
Denver, CO 80202

Well total depth 4030 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface Pipe: 8 5/8 Inch 218 Feet  
W/160 sxs.cmt.

Aband. oil well , Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Murfin Drilling/Allied Cementing License# -

Address: Hill City, Kansas 67642/Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day: 26 Month: October Year 1998

Plugging proposal received from: Roland Nyp

Company: Benchmark Oil & Gas Phone: -

Were: 4 1/2" casing set at 4028' w/125 sxs cement. Perfs at 3954' - 3959'.  
Ordered 225 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.  
Perf anhy at 2000' - Dakota at 1300'. Top of tubing fish at 2012'.

RECEIVED  
KANSAS CORP COM  
1998 NOV - 10 1:25

11/1/98

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All , Part [ ], None [ ]

Completed: Hour: 12:30 P.M., Day 26, Month: October, Year: 1998

Actual plugging report: Perforated casing at 1300' and 2000'. Run in hole with tubing to 1995'. Spotted 105 sxs cement with 400# hulls mixed in cement to circulate at surface with cement. P.O.O.H. with tubing and squeezed 4 1/2" casing with 15 additional sxs to Max. P.S.I. 600#. S.I.P. 500#. R.U. Cementers to 8 5/8" S.P. and squeezed 50 sxs cement with 100# hulls. Max. P.S.I. 150#.

Remarks:

Condition of casing(in hole): GOOD  BAD \_\_\_\_\_ Anhy.plug: YES  NO \_\_\_\_\_  
Bottom plug(in place): YES , CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES , NO \_\_\_\_\_  
Plugged through TUBING  CASING \_\_\_\_\_ Elevation: \_\_\_\_\_ G.L. \_\_\_\_\_

I did  / did not [ ] observe the plugging.

Dennis J. Hamel  
(agent)

Form CP-2/3

11-4-98  
60251