

4-060611

11-14

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-22,750 - 00-00
200' NE NW

SW NW NE /4 SEC. 25, 08 S, 25 W
4390 feet from S section line
2210 feet from E section line
2410 JB-KCC

Operator license# 31136

Lease Waltz well # 1

Operator: Dale F. Haselhorst

County Graham

Address: 2701 Willow
Hays, Kansas 67601

Well total depth 3866 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 210 feet

125.65

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Emphasis Oil Operations License# 8241

Address: Russell, Kansas 67665

Company to plug at: Hour: 2:00A.M. Day: 14 Month: November Year: 94

Plugging proposal received from: Jack Fox

Company: Emphasis Oil Operations Phone:

Were: Order 200 sxs. 60/40 posmix - 6% gel - 1/4# flocele per. sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 2:00A.M., Day: 14, Month: November, Year: 94

Actual plugging report:

- 1st. plug at 2080' w/25 sxs. - Anhydrite 2061' - 2093'.
- 2nd. plug at 1200' w/100 sxs. - Dakota 891' - 1191'.
- 3rd. plug at 260' w/40 sxs. - Surface pit at 210'.
- 4th. plug at 40' w/10 sxs.
- Rathole with 15 sxs.
- Mousehole with 10 sxs.

RECEIVED
STATE CORPORATION COMMISSION
NOV 28 1994
CONSERVATION DIVISION
WICHITA, KANSAS
11/28/94

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC , NO X Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation: 2341 GL

I did and not X observe the plugging.

Herb Deines
(agent)

INVOICED
DATE 12-6-94
INV. NO. 41808