

4-031661

2-21

SR

15-065-20006-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 1967

NW SE /4 SEC. 30, 08 S, 25 W
1980 feet from S section line
1980 feet from E section line

Operator license# 5285

Lease Hansen Estate Fee well # 3

Operator: The Dane G. Hansen Trust

County Graham

Address: Box 187
Logan, Kansas 67646

Well total depth 4000 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 200 feet

130.00

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 21 Month: February Year: 92

Plugging proposal received from: Rich

Company: Hansen Trust Phone:

Were: Order 350 sx. 65/35 pozmix - 10% gel. - 500# hulls.
8 5/8" set @ 200' w/155 sx. 4 1/2" set @ 3999' w/125 sx.
Perf. 3892' - 3936'. Hole open across perf's.

STATE OF KANSAS
COMMISSIONER OF CONSERVATION
LAD - 9 1992

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[X], Part[], None[]

3/9/92

Completed: Hour: 1:35P.M., Day: 21, Month: February, Year: 1992

Actual plugging report: Shots @ 2200' anhy. and 1340' Kiowa.
Squeezed 4 1/2" casing w/700 sx. from 3200' and 2543'. Tested 8 5/8" to
1000#. Locked up, took no fluid. Squeezed 4 1/2" w/300 sx. cement blend
w/400# hulls. Mixed into Max. P.S.I. 700#. Close in P.S.I. 400#.
Plug complete.

Remarks: Plug from 3936' to surface across and into anhy.
Condition of casing(in hole):GOOD X BAD Anhy.plug:YES X NO
Bottom plug(in place):YES , CALC , NO Dakota plug:YES , NO
Plugged through TUBING , CASING . Elevation: 2489 GL

I did[X] / did not[] observe the plugging.

Carl Goodrow

DATE 3-16-92

(agent)

INV. NO. 34743

Form CP-2/3