

4-061087

6-15

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-065-22,785 - 00-00

S2 SW NW /4 SEC. 30, 08 S, 25 W  
2970 feet from S section line  
4620 feet from E section line

Operator license# 5285

Lease: Hansen Estate Fee Well # 8

Operator: Dane G. Hansen Trust

County: Graham 128.38

Address: Box 187  
Logan, Kansas 67646

Well total depth 3950 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 221 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Discovery Drilling License# 31548

Address: Hays, Kansas 67601

Company to plug at: Hour: 4:00 A.M. Day: 15 Month: June Year: 1997

Plugging proposal received from: Tom Alm

Company: Discovery Drilling Phone:

Were: Order 200 sxs 60/40 posmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [ ], Part [ ], None [ X ]

Completed: Hour: 6:30 A.M. , Day: 15, Month: June , Year: 1997

Actual plugging report:

1<sup>st</sup>. Plug at 2175' w/25 sxs. - Anhydrite 2136' - 2171'.

2<sup>nd</sup>. Plug at 1250' w/100 sxs. - Dakota 949' - 1249'.

3<sup>rd</sup>. Plug at 275' w/40 sxs. - Surface pipe to 221'.

4<sup>th</sup>. Plug at 40' w/10 sxs.

Rathole with 15 sxs.

Mousehole with 10 sxs.

RECEIVED  
KANSAS CORP COMM  
JUN 24 12:40  
6/24/97

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC, NO X Dakota plug: YES X, NO

Plugged through TUBING X, CASING. Elevation: 2399 GL

I did [ ] / did not [ X ] observe the plugging.

DATE JUN 25 1997

INV. NO. 48411

6-15

*[Signature]*  
DH (agent)  
Form CP-2/3