

7-29

4-031845

15-065-30242-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 1967

SE SE /4 SEC. 30, 08 S, 25 W
660 feet from S section line
660 feet from E section line

Operator license# 5285

Lease Hansen Estate Fee well # 1

Operator: Dane G. Hansen Trust

County Graham

Address: P.O. Box 187
Logan, Kansas 67646

Well total depth 4040 feet 131.30
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 204 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Hi-Plains License#

Address: Logan, Kansas 67646

Company to plug at: Hour: A.M. Day: 29 Month: July Year: 93

Plugging proposal received from: Rich

Company: Dane G. Hansen Trust Phone:

Were: Ordered 350 sxs. 65/35 pozmix - 10% gel. - 500# hulls.
Allied Cement Company.
Work string of 2 3/8" tubing.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 12:15 P.M., Day: 29, Month: July, Year: 93

Actual plugging report: 8 5/8" set @ 204' w/150 sxs. cwc. 4 1/2" set @ 4039'. P.B.T.D. 4000'. Perf. 3820' - 3986'. Squeezed 3820' - 3986' with 300 sxs. - 1833' w/70 sxs. - 3335' w/67 sxs. - 1813'-1875' w/170 sxs. - 3068'-3100' w/75 sxs. - 1741'-1864' w/45 sxs. - 1759'-1800' w/200 sxs. - 2460'-2672' w/200 sxs. - 2851'-2861' w/200 sxs. - 2310' w/330 sxs. - 3188'-3219' w/300 sxs. Shot @ 1325' Iowa SH. Squeezes across anhy. Ran tubing to 3980' and spotted cement blend slurry w/hulls to surface. Used total of 300 sxs. cement w/500# hulls. Squeezed 4 1/2". Max. P.S.I. 500#. Close in P.S.I. 500#. Squeezed 8 5/8" w/100 sx. cement blend to 2500'.

Remarks: Plug complete.

Condition of casing(in hole): GOOD X, BAD, Anhy. plug: YES X, NO

Bottom plug(in place): YES, CALC, NO, Dakota plug: YES X, NO

Plugged through TUBING X, CASING, Elevation: GL

I did [X] did not [] observe the plugging.

Carl Goodrow

(agent)

Form CP-2/3

INVOICED
DATE 8-30-93
INV. NO. 38512

REC'D 8/30/93 HD