

9-8

6-100419

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-179-20,970-00-00

C S2 SW /4 SEC. 29, 08 S, 26 W  
660 feet from S section line  
3960 feet from E section line

Operator license# 5228 Lease Pratt well # 1

Operator: Parrish Coporation County Sheridan

Address: 100 South Market Well total depth 4000 feet - 130.00  
Suite 200 Conductor Pipe:      inch @      feet  
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 259 feet

Aband. oil well     , Gas well     , Input well     , SWD     , D & A X

Plugging contractor: Abercrombie Drilling, Inc. License# 5422

Address: Wichita, Kansas 67202

Company to plug at: Hour: ? Day:      Month:      Year:     

Plugging proposal received from: Bill Craig

Company: Abercrombie Drilling phone:     

Were: **Spot plugs through drill pipe w/ heavy mud between all plugs.**

1st plug @ 2240 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1375 feet " 100 " Mousehole: 10 sacks

3rd plug @ 300 feet " 40 "

4th plug @ 40 feet " wiper plug & 10 sx

5th plug @     

Plugging Proposal Received by: David K. Wann

Plugging operations attended by agent? All[      ], Part[      ], None[ X ]

Completed: Hour: 11:00 am, Day: 8, Month: September, Year: 1990

Actual plugging report: Hole reported plugged as above.

Order 200sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 2600 GL, Anhydrite depth: 2238 - 2273 feet

Did NOT penetrate Arbuckle, cemented by Allied

I did[      ] / did not[ X ] observe the plugging.

RECEIVED  
STATE CORPORATION COMMISSION  
11-15-1990  
NOV 15 1990

David K. Wann  
David K. Wann P. I. (agent)

INVOICED

DATE NOV 16 1990

INV. NO. 29976

*J. S.*

CONSERVATION DIVISION  
Form CP-2/3