

6-050085

11-4

91
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-179-21,026-00-00

C NW SE /4 SEC. 29, 8 S, 26 W
_____ feet from S section line
_____ feet from E section line

Operator license# 5004

Lease Pratt well # 1

Operator: Vincent Oil Corporation

County Sheridan

128.37

Address: 100 North Main
Suite 500
Wichita, Kansas

Well total depth 3950 feet
Conductor Pipe: _____ inch @ _____ feet
Surface pipe 8 5/8 Inch @ 229 feet

Aband. oil well _____, Gas well _____, Input well _____, SWD _____, D & A X

Plugging contractor: Murfin License# 30606

Address: Wichita, Kansas

Company to plug at: Hour: pm Day: 11 Month: November Year: 1991

Plugging proposal received from: Rodney Farr

Company: Murfin Drilling phone: _____

Were: **Spot plugs through drill pipe w/ heavy mud between all plugs.**

1st plug @ 2190 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1320 feet " 100 " Mousehole: 10 sacks

3rd plug @ 280 feet " 40 "

4th plug @ 40 feet " wiper plug & 10sx

Plugging Proposal Received by: Bruce D. Basye

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 4:00 pm, Day: 4, Month: November, Year: 1991

Actual plugging report: Hole reported plugged as above.

Order 195 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 2544 GL, Anhydrite depth: 2176 - 2209 feet

Did not penetrate Arbuckle, cemented by Allied

I did[] / did not[X] observe the plugging.

Bruce D. Basye
Bruce D. Basye Geologist
(agent)

Form CP-2/3

RECEIVED
STATE CORPORATION COMMISSION
11-12-1991
NOV 12 1991
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE 12-5-91
33938