

4-060317

S-31

225  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-179-21,039-00-00

NE of

100' NE NE SW /4 SEC. 29, 08 S, 26 W  
2051 feet from S section line  
2051 feet from E section line

Operator license# 5004

Lease Pratt well # 2

Operator: Vincent Oil Corporation

County Sheridan

Address: 100 N. Main  
#500  
Wichita, Kansas 67202-1308

Well total depth 3950 feet *128.37*  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 229 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Murfin Drilling Co., Inc. License# 30606

Address: Wichita, Kansas 67202

Company to plug at: Hour: 3:00P.M. Day: 31 Month: May Year: 92

Plugging proposal received from: Keith VanPelt

Company: Murfin Drilling Co., Inc. Phone: \_\_\_\_\_

Were: Order 190 sxs. 60/40 posmix - 6% gel. - 1/4# flocele per sx.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 3:00P.M., Day: 31, Month: May, Year: 92

Actual plugging report:

1st plug at 2200' with 25 sxs. - Anhydrite 2187' - 2220'.  
2nd plug at 1325' with 100 sxs. - Dakota 1024' - 1324'.  
3rd plug at 280' with 40 sxs. - Surface pipe to 229'.  
4th plug at 40' with 10 sxs.  
15 sxs. in rathole.

Remarks: B.J. Services

Condition of casing(in hole): GOOD  BAD  Anhy. plug: YES  NO

Bottom plug(in place): YES , CALC , NO  Dakota plug: YES , NO

Plugged through TUBING , CASING . Elevation: 2549 GL

I did  did not  observe the plugging.

DATE 6-18-92  
INV. NO. 35520

*Herb Deines*

(agent)

Form CP-2/3

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 5 1992  
06-05-1992  
CONSERVATION DIVISION  
Wichita, Kansas