

15-179-20008-00-00

11-21

4-032272

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 1967

SW NE /4 SEC. 30, 08, 26 W
3300 feet from S section line
1980 feet from E section line

Operator license# 5148

Lease: Zeigler Well # 1

Operator: Dreiling Oil, Inc.

County: Sheridan 128.70

Address: P.O. Box 550
Hays, Kansas 67601

Well total depth 3960 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 198 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Co Tools License# 5148

Address: P.O. Box 550 - Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 21 Month: November Year: 1997

Plugging proposal received from: Ivan Edsall

Company: Dreiling Oil, Inc. Phone: -

Were: Order 230 sxs 60/40 pozmix - 10% gel - 500# hulls.

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1997
12-10-1997
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All , Part , None

Completed: Hour: 4:30 P.M., Day: 21 Month: November Year: 1997

Actual plugging report: 8 5/8" set at 198' w/150 sxs cwc. 4 1/2" set at 3959 w/175 sxs. Squeezed from 3200' to 1325' w/1200 sxs. Prod. Perfs 3673' - 3883'. PBTB 3902'. Ran tubing to 3200'. Displaced with 50 sxs cement blend and 150# hulls mixed in. Pulled tubing to 2200'. Displaced 50 sxs cement blend with 150# hulls mixed in. Pulled tubing to 1100' cwc 60 sxs cement. Lay down tubing. Topped off with 10 sxs cement. Squeezed 8 5/8" with 10 sxs cement blend to Max. P.S.I. 200#. Held. Plug complete.

Remarks:
Condition of casing(in hole): GOOD BAD Anhy.plugin: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: _____ GL

I did / did not observe the plugging.

Carl Goodrow
(agent)

INVOICED
DATE DEC 12 1997
INV. NO. 49669