

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-20010-00-00
Spot: SENE Sec/Twnshp/Rge: 30-8S-26W
3300 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: SUTOR Well Number: 1
County: SHERIDAN Total Vertical Depth: 3971 feet

Operator License No.: 5145
Operator Name: DREILING OIL INC
Address: PO BOX 550
HAYS, KS 67601

Conductor Pipe: Size feet:
Surface Casing: Size 8.62 feet: 187
Production: Size 4.5 feet: 3970 *129.06*
Liner: Size feet:

10/11

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/11/00
Plug Co. License No.: 5145 Plug Co. Name: DREILING OIL INC
Proposal Rcvd. from: IVAN EDSALL Company: DREILING OIL INC Phone: (785) 625-8327

Proposed Plugging Method: FILL CSG. TO SURFACE W/CMT. 6-9-81 SQUEEZED 1750-1830 W/200 SX. 7-17-81 SQUEEZED AT 1840 W/150 SX, 7-15-70 SQUEEZED AT 2230 W/200 SX. 2-16-89 SQUEEZED 2750-2937 W/150 SX. 7-18-84 SQUEEZED 2910-40 W/200 SX. 6-15-99 SQUEEZED 2097-3128 & 3210-3252 W/200 SX. 2-27-91 SQUEEZED AT 3145-90.
Ordered 230 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/11/2000 11:15 AM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 187' w/150 sxs cwc. 4 1/2" set at 3970' w/175 sxs.
PBTD 3825'. Prod Perfs 3704' - 3933'. WLP at 3825'.
Casing squeezed at 1750' - 3190' w/1300 sxs.
Squeezed 4 1/2" w/170 sxs cement with 500# hulls mixed in to Max. P.S.I. 1500#. Held.
Squeezed 8 5/8" w/50 sxs cement to Max. P.S.I. 500#. Held.
Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

OCT 26 2000
10-26-2000
CONSERVATION DIVISION
Wichita, Kansas

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed *Carl Goodrow*
(TECHNICIAN)

TD

INVOICED
DATE 10/26/00
INV. NO. 2001060891

Form CP-2/3

OCT 17 2000

