

2-19 15-179-20053-00-00

To: **6 031499**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1967
C NE NW, SEC. 30, T 8 S, R 26 W/EX
4620 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5145
Operator: Dreiling Oil Inc.
Name & Address Box 1000
Victoria, Ks. 67671

Lease Name Sutor Well # 3
County Sheridan 127.07
Well Total Depth 3910 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 160

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cement Co. License Number _____

Address Russell Ks.

Company to plug at: Hour: AM Day: 19 Month: Feb. Year: 19 91

Plugging proposal received from Ivan

(company name) Dreiling Oil (phone) _____

were: 8 5/8 set at 160 w/125 sks cwc. 4 1/2 set at 3906 w/150 sks. Perfs
3633-3840. Shot holes at 1270 and 2130. Order 350 sks 65/35 poz 8% gel
500 lbs. hulls. Allied Cement Co. Company water trucks.
Ran perforating line to 3700.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:50AM Day: 19 Month: Feb. Year: 1991

ACTUAL PLUGGING REPORT Sq 4 1/2 casing w/250 sks cement blend w/500 lbs. hulls
mixed into max psi 600 lbs. Close in psi 500 lbs.
Sq 8 5/8 w/100 sks cement blend to max psi 150 lbs. Close in psi 150 lbs.
Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
3-13-1991
MAR 13 1991

Remarks: _____ (If additional description is necessary, use BACK of this form)
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 3-15-90
INV. NO. 31180

Feb. 5

Signed Carl Goodrow
(TECHNICIAN)