

15-179 20059-00-00
2-19

6 031498

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
C NW NE, SEC. 30, T 8 S, R 26 W/E
4620 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5145

Lease Name Zeigler Well # 3
County Sheridan 128.24
Well Total Depth 3946 feet
Conductor Pipe: Size 8 5/8 feet 140
Surface Casing: Size 8 5/8 feet 140

Operator: Dreiling Oil Inc.
Name & Address Box 1000
Victoria, Ks. 67671

Abandoned Oil Well xx Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement Co. License Number
Address Russell, Ks.

Company to plug at: Hour: PM Day: 10 Month: Feb. Year: 19 91

Plugging proposal received from Ivan
(company name) Dreiling Oil (phone)

were: 8 5/8 set at 140 w/100 sks cwc. 4 1/2 set at 3944 w/150 sks. Perf 3731 - 3867.
Sq at 1966 w/450 sks. Sq at 2289 w/150 sks. and at 3098 w/200 sks. Order 350
sks 65/35 poz 8% gel 500 lbs. hulls. allied Cement Co. Company water trucks.
Ran perforating line to 3700.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All xx Part None

Operations Completed: Hour: 1:30PM Day: 19 Month: Feb. Year: 19 91

ACTUAL PLUGGING REPORT Sq 4 1/2 w/259 sks cement blend w/400 lbs.

hulls mixed into max psi 300 lbs. Close in psi 150 lbs.
Sq 8 5/8 w/100 sks cement blend to max psi 150 lbs. Close in psi
150 lbs. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
3-13-1991
MAR 13 1001

Remarks: If additional description is necessary, use BACK of this form.

INVOICED
DATE 3-15-91
INV. NO. 31171

I did / did not observe this plugging.
G.S.

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow

CONSERVATION DIVISION
WICHITA, KANSAS