

9-25

226

R

6-031589

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-179-21,020-00-00
110'NW of
SE SE SE 1/4 SEC. 31, 8 S, 26 W
440 feet from S section line
440 feet from E section line

Operator license# 5011 Lease Schamberger well # 1

Operator: Viking Resources Inc. County Sheridan

Address: 105 S. Broadway Well total depth 3980 feet
Suite 1040 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 262 feet

129.35

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Mallard J.V. Inc. License# 4958

Address: McPherson, Kansas

Company to plug at: Hour: P.M. Day: 25 Month: September Year: 91

Plugging proposal received from: Arnie Hess

Company: Mallard J.V. Inc. Phone: _____

Were: 8 5/8" set @ 262' w/170 sx. cwc. Spot plugs with drill pipe
with no less than 36 vis. mud between all plugs with good circulation
and no fluid loss. Order 200 sx. 60/40 poz. - 10% gel. - 3% c.c. -
8 5/8" W.P. Allied Cement Company.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 5:30P.M. Day: 25 Month: September Year: 91

Actual plugging report:
1st. plug @ 2275' w/25 sx.
2nd. plug @ 1350' w/100 sx. and hulls.
3rd. plug @ 310' w/40 sx.
4th. plug @ 40' w/10 sx. W.P.

Circ. 15 sx. in rathole.
Circ. 10 sx. in mousehole.

Remarks: _____

INVOICED [did not] [did not] [X] observe the plugging. Carl Goodrow

DATE 11-8-91

INV. NO. 33657

Carl S. 11-20-1991 (agent)

9-25 - NOV 20 1991