

6 031280

6-26  
API NUMBER 15- 179-20,945-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW NW SE, SEC. 34, T 8 S, R 26 W/E  
2310 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5011

Lease Name Pratt Well # 1

Operator: Viking Resources

County Sheridan 126.52

Name & Address 120 S. Market Suite 518

Well Total Depth 3893 feet

Wichita, Ks. 67202 - 3819

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 204

Abandoned Oil Well Gas Well Input Well SWD Well U&A X

Other well as hereinafter indicated

Plugging Contractor Mallard J. V. Inc. License Number 4958

Address McPherson, Ks.

Company to plug at: Hour: PM Day: 26 Month: June Year: 19 89

Plugging proposal received from Bryon Hess

(company name) Mallard (phone)

were: 8 5/8" set at 204' w/140 sks cwc. Circ hole w/no less than 36 vis mud w/

no loss or gain in fluids. Balance plugs and keep hole full w/mud. Order 200 sks  
60/40 poz 6% gel 3% cal cl 8 5/8" wiper plug. Hulls. Allied Cement Co.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:15PM Day: 26 Month: June Year: 19 89

ACTUAL PLUGGING REPORT Spot cement plugs w/drill pipe

at 2175' w/25 sks. 1250' w/100 sks hulls

250' w/40 sks

40' w/10 sks wiper plug

15 sks in rathole

10 sks in mousehole

RECEIVED  
STATE CORPORATION COMMISSION

AUG 14 1989

8-19-1989  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Elev. 2538' G.L. Anhy 2159 - 92  
(If additional description is necessary, use BACK of this form.)

(If possible, observe this plugging.)

Signed Carl Goodrow  
(TECHNICIAN)

Carl Goodrow

DATE 8-17-89

INV. NO. 25669