

4-090518

6-16

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-179-21,071-00-00

SW NW NE /4 SEC. 34 , 08 S, 26 W
4290 feet from S section line
2310 feet from E section line

Operator license# 5472 Lease Pratt well # 1

Operator: Hoppe Oil & Gas Co., Inc. County Sheridan

Address: 212 N. Market Well total depth 3960 feet ^{128.70}
Suite 315 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 262 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Mallard J.V., Inc. License# 4958

Address: McPherson, Kansas 67460

Company to plug at: Hour: - Day: 13 Month: June Year: 94

Plugging proposal received from: Carol Nickel

Company: Mallard J.V., Inc. Phone: 316-241-4640

Were: Order 200 sxs. 60/40 posmix - 6% gel - 2 sxs. celloflake.
Spot all plugs through drill pipe with heavy mud between all plugs.

Plugging Proposal Received by: Ed Schumacher
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 2:00A.M., Day: 16, Month: June, Year: 94

Actual plugging report:
1st. plug at 2200' w/25 sxs. cement.
2nd. plug at 1330' w/100 sxs. cement.
3rd. plug at 315' w/40 sxs. cement.
4th. plug at 40' w/10 sxs. cement.
10 sxs. in rathole.
15 sxs. in mousehole.

Remarks: By: Allied Cementing - Arbuckle No.
Condition of casing(in hole): GOOD BAD Anhy. plug: YES 2179 NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 2553' GL

I did did not observe the plugging. Ed Schumacher

INVOICED

DATE 6-29-94
INV. NO. 40706

Received: 6-29-1994

(agent)
Form CP-2/3