

6 070302

API NUMBER 15-179-20, 815-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION NE-NW-SW, SEC. 25, T. 8 S, R. 26  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

2310 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name Senger Well # 1

Operator: Chief Drilling Co. Inc.

County Sheridan 127.73

Name & Address 905 Century Plaza Bldg

Well Total Depth 3930 feet

Wichita, Kans.

Conductor Pipe: Size 0 feet

67202

Surface Casing: Size 8 5/8 feet 241

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated Tag-279

Plugging Contractor Warrior Drilling Co Rig #1 License Number 5883

Address Wichita, Kans.

Company to plug at: Hour: 8:30 PM Day: 22<sup>nd</sup> Month: May Year: 19 85

Plugging proposal received from Harold Duntel

(company name) Warrior Drilling Co. (phone) 716-262-3791

were: 8 5/8" 241' EX SR. CUL. #165 SK 60/40 Pozmix Gel-Co-cl. - BY Allied Cont.

Order 200 SK 50/50 Pozmix Gel-Co-cl. - 1 SK Cello and 8 5/8" Plug

spot with Drill Stem, Recondition Hole (45 Vis) Heavy Mud Between All Plugs

HC-MISS. Well, No Circulation Problems, Mud Condition 9.8 - 45 Vis.

ELV. 2528 - Only 2158

RECEIVED STATE CORPORATION COMMISSION MAY 28 1985

Plugging Operations Proposed Received by Marion Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All  None

Operations Completed: Hour: 8:30 PM Day: 22<sup>nd</sup> Month: May Year: 19 85

ACTUAL PLUGGING REPORT

Ordered 200 SK 50/50 Pozmix Gel-Co-cl. - 1 SK Cello and 1 8 5/8" Plug.

Spotted with Drill Stem, Reconditioned Well, Heavy Mud Between All Plugs

1<sup>st</sup> Plug @ 2170 FT #1/30 SK cont, 2<sup>nd</sup> Plug @ 1310 FT #1/100 cont 1 SK Cello

3<sup>rd</sup> Plug @ 270 FT #1/50 SK cont, 4<sup>th</sup> Plug Solvent Bridge @ 40 FT #1/10 SK cont.

10 SK IN cat hole (circulate) Cemented by Allied Cont

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-29-85

INV. NO. 8293

Signed Marion Schmidt (TECHNICIAN)  
Bob