

1-24

4-020126

API number: 15-179-21.089-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

10'W S2 SW SE /4 SEC. 35 , 08 S, 26 W
330 feet from S section line
1990 feet from E section line

Operator license# 06622

Lease: Sanger Well # 1

Operator: Jason Oil Company
Address: P.O. Box 701
Russell, Kansas 67665-0701

County: Sheridan 129.35
Well total depth 3980 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 250 feet

Aband. oil well _____, Gas well _____, Input well _____, SWD _____, D & A X

Plugging contractor: Discovery Drilling, Inc. License# 31548

Address: P.O. Box 763, Hays, Kansas 67601

Company to plug at: Hour: _____ Day: 24 Month: January Year: 1997

Plugging proposal received from: Tom w/Discovery

Company: Discovery Drilling, Inc. Phone: 913 623 2920

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2210 feet with 25 sacks	Rat hole: 15 sacks
2nd plug @ 1320 feet with 100 sacks	Mouse hole: 10 sacks
3rd plug @ 300 feet with 40 sacks	
4th plug @ 40 feet with 10 sacks	

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 05 1997 2:16
02-03-1997

Plugging Proposal Received by: Ken Kuhn
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 10:00 AM, Day: 24, Month: January, Year: 1997

Actual plugging report: Hole reported plugged as above.

Order 200 sx 60/40 pozmix w/ 6% gel and 2.0 sx celloflake or flowcel.

Remarks: Allied Cementing performed the cement job.
Condition of casing(in hole): GOOD X BAD _____ Anhy.plug: YES X NO _____
Bottom plug(in place): YES X, CALC _____, NO _____ Dakota plug: YES X, NO _____
Plugged through TUBING _____, CASING X. Elevation: 2548 GL

I did[] / did not[X] observe the plugging.

INVOICED
FEB 05 1997

Ken Kuhn
(agent)

Form CP-2/3

DATE _____

INV. NO. 47518
1-24