

10-17

293

R

4-070967

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-179-21,024 -0000

N2 NW SE /4 SEC. 32, 08 S, 27 W  
2310 feet from S section line  
1980 feet from E section line

Operator license# 30805 Lease Welling well # 1

Operator: Welling Heirs County Sheridan 129.18

Address: 401 Ash Well total depth 3975 feet  
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet  
W.D. Welling Surface pipe B 5/8 Inch @ 223 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Emphasis Drilling License# B241

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 17 Month: October Year: 91

Plugging proposal received from: John Collins

Company: Emphasis Drilling, Russell, Ks Phone: 913-625-2204

Were: B 5/8" - 223' S.P. cwc w/170 sks. 60/40 posmix - 2% gel. -  
3% c.c. By Allied. K.C. Well. Elv. 2576' - Anhy. 2204' - No cir.  
problems - 48 vis. - 9.0 weight - 8.9 W.L. Proposal 200 sks. 60/40  
posmix - 6% gel. - 3% c.c. Spot with drill stem. Circulate hole.  
Heavy mud between all plugs. 25 sks. @ 2210' - 100 sks. w/1 F.C. @  
1370' - 40 sks. @ 270' - 10 sks. @ 40' - 15 sks. rathole - 10 sks.  
mouse hole. Circulate.

Plugging Proposal Received by: Marion J. Schmidt  
Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 6:15A.M. Day: 17 Month: October Year: 91

Actual plugging report: Welling ordered 200 sks. 60/40 posmix - 6% gel.  
3% c.c. Circulated hole. Spotted cement with drill stem. Heavy mud  
between all plugs.

1st. plug @ 2210' w/25 sks. cement.  
2nd. plug @ 1370' w/100 sks. cement w/1 sk. F.C.  
3rd. plug @ 270' w/40 sks. cement.  
4th. plug @ 40' w/10 sks. cement.  
15 sks. in Rathole. - 10 sks. in Mousehole. (Circulated

RECEIVED  
STATE CORPORATION COMMISSION

NOV 4 1991 11/4/91

Remarks: Cemented by: Allied.

CONSERVATION DIVISION  
Wichita, Kansas

I did[  ] did not[  ] observe the plugging.

*Marion J. Schmidt*  
(agent)

*Gilda S.*

Form CP-2/3

INVOICED

DATE 11-15-91

INV. NO. 33749