

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-179-20714-00-00 ✓
SE, Sec. 34, T 8 S, R 27 W/4
_____ feet from N/S section line
_____ feet from W/E section line P

TECHNICIAN'S PLUGGING REPORT

Operator License # 6889

Lease Name Mosier Well # 34-15-2

Operator: Oxford Exp
Name & Address: 1550 Denu. C16. Bldg.
Denver Colo.

County Sheridan

Well Total Depth 4030 feet / 30.98

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 252

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Warrior Drilg. Co. License Number 5883

Address 905 Cent. Plz. Wichita KS.

Company to plug at: Hour: 3 PM Day: 4 Month: 12 Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Harold Dinkel

(company name) Warrior Drilg. Co. (phone) 913 726-4875

were: order 185 sx cem. 50/50 pozmix 6% gel. 3% c.c.
mixed with 2sx Flow Seal- 15x hulls, 1-8 5/8 plug
Heavy mud between all plugs.

Pump cem. down drill pipe

Elev. 2639 Anhydrite 2240-76 Arbuckle No

Dakota 1500 Signed Dale Balthezor (TECHNICIAN)
1139 = 1440

Plugging Operations attended by Agent?: All _____ Part None

Operations Completed: Hour: 7: PM Day: 4 Month: 12 Year: 1983

ACTUAL PLUGGING REPORT circ. @ 2260 Turn hole over

25 sx @ 2260

100 sx @ 1440

40 sx @ 300 - 15x hulls push plug to 40'

10 sx @ 40

10 sx in Rat hole

Remarks: _____

Cementing 20 - Allied

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / did not) observe this plugging.

INVOICED

DATE 1-10-84 RECEIVED STATE CORPORATION COMMISSION

INV. NO. 8185 W DEC 12 1983 12-12-83

Signed Dale Balthezor (TECHNICIAN) ✓