


15-065-20149-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Graham County. Sec. 28 Twp. 8S Rge. 25W ~~NE~~ W (W)
Location as "NE/CNW/SW" or footage from lines NW SE NW
Lease Owner Bankoff Oil Company and Leben Drilling, Inc.
Lease Name Culley #1 Well No. 1
Office Address P. O. Box 486 - Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed 6-6 1968
Application for plugging filed 6-6 1968
Application for plugging approved 6-6 1968
Plugging commenced 6-6 1968
Plugging completed 6-6 1968
Reason for abandonment of well or producing formation Dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols - Morland, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3885 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	201.18	None


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug @ 1235' w/100 sx 50-50 Pos. 6% Gel.
Set plug @ 210' w/20 sx 50-50 Poz. 6% Gel.
Set plug @ 40' w/ 1/2 sx hulls 10 sx Cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 14 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Leben Drilling, Inc.
Address P. O. Box 486 - Great Bend, Kansas 67530 6-14-68

STATE OF Kansas, COUNTY OF Barton, ss.
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) Leslie Kite
P. O. Box 486 - Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of June, 19 68
Ulanda Nichols Notary Public.
My commission expires April 1, 1971

COMPANY
CONTRACTOR
FARM
LOCATION

Bankoff Oil Company
LEBEN DRILLING, INC.
CULLEY #1
NW SE NW Section 28-8s-25w
Graham County, Kansas
6-1-68
6-6-68

COMMENCED
COMPLETED

0	70	Clay - Sand
70	1060	Sand and Shale
1060	1163	Hard Sand - Shale
1163	1855	Sand and Shale
1855	2198	Shale and Red Bed
2198	2228	Anhydrite
2228	2245	Shale
2245	2590	Shale and Shells
2590	3660	Lime and Shale
3660	3885	Lime
	3885	RTD - D & A

8 5/8" New 20# Surface Casing - Set @ 209' with 165 sx common 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Culley #1 Well, located NW SE NW of Section 28, Township 8 South, Range 25 West, Graham County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 12th day of June, 1968.

Ulanda Nichols

Ulanda Nichols-Notary Public

My Commission Expires
April 1, 1971

