

15-065-02029-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

GRAHAM

County. Sec. 31 Twp. 8S Rge. 25W (E) (W)

Location as "NE/CNW%SW%" or footage from lines SE SE SE

Lease Owner HARPER OIL COMPANY

Lease Name ZOHRER Well No. 1

Office Address 904 Hightower Building, Oklahoma City, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed May 30th, 1959 19

Application for plugging filed May 30th, 1959 19

Application for plugging approved May 30th, 1959 19

Plugging commenced May 30th, 1959 19


Plugging completed May 30th, 1959 19

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well _____

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4103' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	225'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with heavy mud to 500' set plug with 20sx cement thru drill pipe. Filled with heavy mud to 220' set plug with 20 sx cement thru drill pipe. Filled with heavy mud to 40' set solid bridge with 1/2 sx hulls & 10 sx cement to base of callar. Job Complete 5-30-59

RECEIVED
STATE CORPORATION COMMISSION

JUN 4 1959

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor K & E DRILLING, INC. Address 719 Union Center, Wichita 2, Kansas 6-4-59

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Dale Silcott (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale Silcott
Dale Silcott, of K & E DRILLING, INC.
719 Union Center, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of June, 1959

My commission expires August 11th, 1962.
Patricia M. Edwards, Notary Public.



PLUGGING
FILE SEC. 31 T. P R. 25W
BOOK PAGE 42 LINE 6

DRILLER'S WELL LOG

OPERATOR: HARPER OIL COMPANY
904 Hightower Building
Oklahoma City, Oklahoma

WELL NAME: #1 ZOHNER
LOCATION: SE SE SE,
Sec. 31-8S-25W
GRAHAM CO, KANSAS

CONTRACTOR: K & E DRILLING, INC.
719 UNION CENTER BLDG.
WICHITA, KANSAS

COMMENCED: May 23rd, 1959

CASING RECORD: 8-5/8" @ 225' (160 sx cmt)

COMPLETED: May 30th, 1959

ELEVATION: unknown

ROTARY TOTAL DEPTH: 4103'

PRODUCTION: D & A

FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Cellar	8
Clay & Shale	60
Sand & Shale	135
Shale & Shells	225
Shale	465
Shale & Shells	1310
Shells & Shale	1865
Sand	2050
Shale	2270
Anhydrite	2365
Shale & Shells	2670
Shale & Lime	2815
Lime	2985
Lime & Shale	3170
Lime	3425
Lime & Shale	3560
Lime	3720
Lime & Shale	3845
Lime	4103
R.T.D.	4103

RECEIVED
STATE CORPORATION COMMISSION

JUN 4 1959

CONSERVATION DIVISION
Wichita, Kansas

64-59

CERTIFICATION

State of KANSAS }
County of SEDGWICK } ss:

I, DALE SILCOTT, of K&E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.


Dale Silcott

Dale Silcott

Subscribed and sworn to before me this 3rd day of June, 1959.

Patricia M. Edwards

Patricia M. Edwards, Notary Public.



PLUGGING
FILE SEC 31 T 8 R 26W
BOOK PAGE 43 LINE 6

