


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202  
NORTH

WELL PLUGGING RECORD

Sheridan County, Sec. 30 Twp. 8 Rge. 26 (E) W (W)  
Location as "NE/CNW%SW%" or footage from lines NW NW  
Lease Owner Dreiling Oil, Inc.  
Lease Name Sutor Well No. 4  
Office Address R.R. # 2 Victoria, Kansas 67671  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed February 1 19 72  
Application for plugging filed February 1 19 72  
Application for plugging approved February 1 19 72  
Plugging commenced February 1 19 72  
Plugging completed February 1 19 72  
Reason for abandonment of well or producing formation Dry



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production January 20 1972  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well ~~DEK WASSER~~ Bill Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3,930' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	Surface Pipe	0	163	8 5/8"	163	0
Casing	Casing	0	3,922	4 1/2"	3,922'	906'


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged with 4 sacks hulls, 12 sacks gel, 110 sacks cment, 16 sacks gel, 30 sacks cement, 2 sacks gel, and 10 sacks cement. Input 400# pressure.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 18 1972  
CONSERVATION DIVISION  
Wichita, Kansas  
2-18-19 72

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Dreiling Oil, Inc.  
Address R.R. # 2 Victoria, Kansas 67671

STATE OF Kansas, COUNTY OF Ellis, ss.  
I, Leo F. Dreiling, Pres. of Drlg. Contrc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.



(Signature) Leo F. Dreiling  
LEO F. DREILING, R.R. #2, Victoria, Kansas 67671  
(Address)

SUBSCRIBED AND SWORN to before me this 15 day of February, 19 72

Joseph A. Hess  
JOSEPH A. HESS Notary Public.

L. J. DREILING and SONS, Inc.  
VICTORIA, KANSAS

WELL LOG

Company	Leo J. Dreiling Oil Company Route 2 Victoria, Kansas 67671	Sec. 30	Twp. 8	Rng. 26
Farm	Sutor No. 4	Location	NW NW	
Total Depth	3930'	County	Sheridan	
Comm.	5-9-68 Comp. 5-28-68	Elevation:	2529'	K.B.
Contractor	L. J. Dreiling & Sons, Inc. Route 2 Victoria, Kansas 67671		2526'	D. F.
	Casing Record	Cement Record	2524'	G. R.
	163' - 8 5/8"	125 sacks cement		
	3921.97 - 4 1/2"	150 sacks cement		
		Production:		

Figures Indicate Bottom of Formations

0'	163'	Surface Soil
163'	650'	Shale & Shells
650'	1633'	Shale
1633'	1760'	Shale
1760'	1924'	Sand
1924'	2149'	Shale & Redbed
2149'	2180'	Anhy.
2180'	2655'	Shale
2655'	3367'	Lime & Shale
3367'	3420'	Shale & Lime
3420'	3730'	Lime & Shale
3730'	3930'	Lime
3930'	T.D.	

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 9 1972  
CONSERVATION DIVISION  
Wichita, Kansas  
2-9-1972

STATE OF KANSAS)  
                                  )ss  
COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Sutor #4.

*Leo F. Dreiling*  
\_\_\_\_\_  
LEO F. DREILING

Subscribed and sworn to before me this 28th day of May 1968.

*Joseph A. Hess*  
\_\_\_\_\_  
JOSEPH A. HESS NOTARY PUBLIC



My Commission expires: September 19, 1970