


15-179. 05217-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Sheridan

County. Sec. 32 Twp. 8S Rge. (E) 26W (W)

Location as "NE/CNW/SE" or footage from lines SW NE NE

Lease Owner Pickrell Drilling Company

Lease Name Hoxie State Bank

Well No. # 1

Office Address 2820 Paseo Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19 _____

Application for plugging filed yes _____ 19 _____

Application for plugging approved yes _____ 19 _____

Plugging commenced 12-6-60 _____ 19 _____

Plugging completed 12-10-60 _____ 19 _____

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3890' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		1,094'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugging commenced 12-6-60. Plugging completed 12-10-60.

Measured in to total depth: 3890'

Plugged off bottom: Sanded back to 3870' and dumped 5 sacks of cement.

Worked and shot casing. Loaded hole with water. Worked and shot 5 1/2" casing free at 1,094'. Built rack and slide.

Pulled and layed down casing.

Plugged well: Mudded hole up to 150' and set 10' rock bridge.

Dumped 25 sacks of cement. Mudded hole up to 40' and set 5' ~~XXX~~ rock bridge. Capped the well with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J. O. Forbes d/b/a Forbes Casing Pulling Company

Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

J. O. Forbes

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. (So help me God.)

(Signature)

J. O. Forbes
P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of December, 19 60

My commission expires December 8th, 1963

Kayam Jenkins
Notary Public.



Well #1

LOG

COMPANY: EMPIRE DRILLING COMPANY
CONTRACTOR: EMPIRE DRILLING COMPANY
FARM: HOXIE STATE BANK #1
LOCATION: SW NE NE, SEC. 32-65-26N
 SHERIDAN COUNTY, KANSAS
COMMENCED: 11/24/54
COMPLETED: 12/5/54

0	TO	163	SURFACE MUD
163	TO	210	SHALE
210	TO	2130	SHALE AND SHELLS
2130	TO	2165	ANHYDRITE
2165	TO	2255	SHALE AND SHELLS
2255	TO	2385	SHALE AND LIME
2385	TO	2988	SHALE AND SHELLS
2988	TO	3170	LIME AND SHALE
3170	TO	3239	SHALE AND LIME
3239	TO	3670	LIME AND SHALE
3670	TO	3742	LIME
3742	TO	3790	LIME AND SHALE
3790	TO	3825	LIME
3825	TO	3845	LIME AND SHALE
3845	TO	3890	LIME
3890			R.T.D.

GET 150' OF 3-5/8" SURFACE CASING, CEMENTED WITH 115 BAGS OF CEMENT.

ELEVATION: 2328 K. B.

TOPS: ANHYDRITE 2130'; HEEBNER 3618'; TORONTO 3658'; L.S. K.C. 3853'; R.T.D. 3890'.

RAN 3890' - 5 1/2" CASING, CEMENTED WITH 75 BAGS OF CEMENT.

C E R T I F I C A T I O N

I, DAN J. KORNFIELD, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE HOXIE STATE BANK #1, SW NE NE, SECTION 32, TOWNSHIP 6 NORTH, RANGE 29 WEST, SHERIDAN COUNTY, KANSAS AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.

Dan J. Kornfield
DAN J. KORNFIELD

SUBSCRIBED AND SWORN TO BEFORE ME A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS THIS 18TH DAY OF DECEMBER 1954.

MY COMMISSION EXPIRES MAY 5, 1958

Mary Hammett
NOTARY PUBLIC

RECEIVED
STATE REGISTRATION COMMISSION
DEC 28 1954
12-28-1960
REGISTRATION DIVISION