

15-179-05218-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Sheridan County. Sec. 32 Twp. 8S Rge. (E) 26W(W)

Location as "NE/CNW/SW" or footage from lines NE SE NE

Lease Owner Pickrell Drilling Company

Lease Name Hoxie State Bank Well No. # 2

Office Address 2820 Paseo Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_

Date well completed \_\_\_\_\_ 19 \_\_\_\_\_

Application for plugging filed yes 19 \_\_\_\_\_

Application for plugging approved yes 19 \_\_\_\_\_

Plugging commenced 12-3-60. 19 \_\_\_\_\_

Plugging completed 12-8-60. 19 \_\_\_\_\_

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3923' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		1,251'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugging commenced 12-3-60. Plugging completed 12-8-60.  
~~XXXX~~ Measured in to total depth, 3923'.  
Plugged off bottom: Sanded back to 3915' and dumped 4 sacks of cement.  
Worked and shot casing. Spotted oil. Worked and shot casing, 5 1/2" free at 1251'. Built rack and slide. Pulled and layed down casing. Plugged well: Plugged hole with mud up to 175' and set 10' rock bridge. Dumped 25 sacks of cement. Mudded hole up to 40'. Set 10' rock bridge and capped the well with 10 sacks of cement.

DEC 28 1960  
12-28-1960  
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor J. O. Forbes d/b/a Forbes Casing Pulling Company Wichita, Kansas  
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes  
J. O. Forbes  
Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 16th day of December 19 60  
My Commission expires December 8th, 1963  
Kayann Jenkins  
Kayann Jenkins  
Notary Public.



Well #2

LOG

COMPANY: EMPIRE DRILLING COMPANY  
 CONTRACTOR: EMPIRE DRILLING COMPANY  
 FARM: HOXIE STATE BANK #2  
 LOCATION: NE SE NE SEC. 32-8-28  
 SHERIDAN COUNTY, KANSAS  
 COMMENCED: 6-19-55  
 COMPLETED: 6-29-55

0	TO	135	SURFACE
135	TO	195	SHALE AND SHELLS
195	TO	1210	SHALE AND SAND
1210	TO	1483	SHALE AND PYRITE
1483	TO	1489	SAND AND PYRITE (HARD)
1489	TO	2100	SHALE REDDED
2100	TO	2157	SHALE AND SHELLS
2157	TO	2190	ANHYDRITE
2190	TO	2565	SHALE AND SHELLS
2565	TO	3650	LIME AND SHALE
3650	TO	3680	LIME
3680	TO	3915	LIME AND SHALE
3915	TO	3923	LIME
3923			R.T.D.

SET 8 5/8" SURFACE CASING AT 178' WITH 115 BAGS OF CEMENT.

ELEVATION: 2550-K-8.

TOPS: ANHYDRITE 2157'; HEEBNER 3646'; TORONTO 3668'; LANING 3682'; BASE K. C. 3900'; R.T.D. 3923'.

D.S.T. #1 3800 TO 3816'; D.S.T. #2 3820 TO 3845'; D.S.T. #3 3857 TO 3880'; D.S.T. #4 3748 TO 3780'.

RAN 5 1/2" CASING SET AT 3923' WITH 75 BAGS CEMENT.

CERTIFICATION

I, DAN J. KORNFELD, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE HOXIE STATE BANK #2, NE SE NE, SECTION 32, TOWNSHIP 8 SOUTH, RANGE 28, SHERIDAN COUNTY, KANSAS, AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.

DAN J. KORNFELD

SUBSCRIBED AND SWORN TO BEFORE ME A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS, THIS 5TH DAY OF JULY, 1955.

MY COMMISSION EXPIRES DECEMBER 10, 1956

NOTARY PUBLIC

RECEIVED  
ST. T. CORPORATION COMMISSION

DEC 28 1960  
12-28-1960  
CONSERVATION DIVISION  
Wichita, Kansas