

Vincenti Innone dba

Operator Name: VIA NATURAL RESOURCES, INC. Lease Name: HOLLEY Well #: 1-A
 Sec. 25 Twp. 8 S. R. 25 East West County: GRAHAM

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken Yes No
 (Attach Additional Sheets)

Samples Sent to Geological Survey Yes No

Cores Taken Yes No

Electric Log Run Yes No
 (Submit Copy)

List All E. Logs Run:
 Radiontation Guard Log
 ELI Wireline-Correlation Log

<input checked="" type="checkbox"/> Log	Formation (Top), Depth and Datum	<input type="checkbox"/> Sample
Name	Top	Datum
Anhy	2112-48	280
Heebner	3680	-1284
Toronto	3704	-1308
LKC	3718	-1322
BKC	3940	-3942
RTD	3979	-1583

CASING RECORD <input type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
SURFACE	12/1/4	8 5/8	20	205	60/40 POZ	150	3% CC 2% Gel
PRODUCTION	7 7/8	5 1/2	15	3980	SMAC	450	113# Flocele

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate				
<input type="checkbox"/> Protect Casing				
<input type="checkbox"/> Plug Back TD				
<input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4shots per/ft	3876-80 3893-97	500mca 2000 20% FENE 5000 20% FENE	

TUBING RECORD Size 2 3/8 Set At 3925 Packer At _____ Liner Run Yes No

Date of First, Resumerd Production, SWD or Enhr. _____ Producing Method Flowing Pumping Gas Lift Other (Explain)

Estimated Production Per 24 Hours Oil Bbls. N/A Gas Mcf _____ Water Bbls. _____ Gas-Oil Ratio _____ Gravity _____

Disposition of Gas **METHOD OF COMPLETION** Vented Sold Used on Lease Open Hole Perf. Dually Comp. Commingled _____
 (If vented, Sumit ACO-18.) Other (Specify) _____

ALLIED CEMENTING CO., INC.

12278

Federal Tax I.D.# [REDACTED]

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT

15-065-22898-00-00

Cakley

DATE <u>3-23-03</u>	SEC. <u>31</u>	TWP. <u>8s</u>	RANGE <u>24w</u>	CALLED OUT	ON LOCATION <u>5:15 PM</u>	JOB START <u>7:40 AM</u>	JOB FINISH <u>8:00 PM</u>
LEASE <u>Holley</u>	WELL # <u>1-A</u>	LOCATION <u>Moreland 4 1/2 S 3 E 1/2 N</u>			COUNTY <u>Graham</u>	STATE <u>K.S.</u>	
OLD OR NEW (Circle one) <u>NEW</u>				<u>2 WNW 1W</u>			

CONTRACTOR A & A Drilling Co
 TYPE OF JOB Surface
 HOLE SIZE 12 1/4 T.D. 210'
 CASING SIZE 8 1/2 DEPTH 208'
 TUBING SIZE DEPTH
 DRILL PIPE DEPTH
 TOOL DEPTH
 PRES. MAX MINIMUM
 MEAS. LINE SHOE JOINT
 CEMENT LEFT IN CSG. 15'
 PERFS.
 DISPLACEMENT 12.30 Bbls

OWNER Same
 CEMENT AMOUNT ORDERED
1500 lbs 60/40 Poz. 30 cc 2 1/2 GEL
 COMMON 90 SKS @ 1.65 598.50
 POZMIX 60 SKS @ 3.55 213.00
 GEL 3 SKS @ 10.00 30.00
 CHLORIDE 5 SKS @ 30.00 150.00
 @
 @
 @
 @
 @
 @
 HANDLING 158 SKS @ 1.10 173.80
 MILEAGE 48 per SK/mile 410.80
 TOTAL 1576.10

EQUIPMENT

PUMP TRUCK CEMENTER Dean
 # 191 HELPER Andrew
 BULK TRUCK
 # 315 DRIVER Fuzzy
 BULK TRUCK
 # DRIVER

REMARKS:

SERVICE

Cement did circulate ✓
Thank you

DEPTH OF JOB
 PUMP TRUCK CHARGE 520.00
 EXTRA FOOTAGE @
 MILEAGE 65 mps @ 3.00 195.00
 PLUG 8 1/2 surface @ 45.00
 @
 @
 TOTAL 760.00

CHARGE TO: V.J.T Natural Resources
 STREET
 CITY STATE ZIP

FLOAT EQUIPMENT


@
 @
 @
 @
 @

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TOTAL
 TAX
 TOTAL CHARGE
 DISCOUNT IF PAID IN 30 DAYS

SIGNATURE [Signature]

PRINTED NAME



CHARGE TO: **V.J.I.**
 ADDRESS:
 CITY, STATE, ZIP CODE:

TICKET No 5373

PAGE 1 OF 2

SERVICE LOCATIONS 1. NESS CITY, KS	WELL/PROJECT NO. A-1	LEASE HOLLEY	COUNTY/PARISH GRAHAM	STATE KS	CITY	DATE 4-2-03	OWNER SAME
2.	TICKET TYPE <input checked="" type="checkbox"/> SERVICE <input type="checkbox"/> SALES	CONTRACTOR A-A DRILLING	RIG NAME/NO.	SHIPPED VIA CT	DELIVERED TO LOCATION	ORDER NO.	
3.	WELL TYPE OIL	WELL CATEGORY DEVELOPMENT	JOB PURPOSE 5 1/2" LONGSTRONG	WELL PERMIT NO.	WELL LOCATION SE/MORNING, KS		
4. REFERRAL LOCATION	INVOICE INSTRUCTIONS						

15-065-22878-0500

RECEIVED
MAY 29 2003
KCC WICHITA

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.		UM		UNIT PRICE	AMOUNT
		LOC	ACCT	DF							
575		1			MILEAGE # 154	70		MC		2.50	175.00
578		1			PUMP SERVICE	1		JOB	3980	1200.00	1200.00
221		1			ATWOOD VCL	2		GAL		19.00	38.00
281		1			MUDFLUSH	500		GAL		.60	300.00
400		1			GUIDE SHOE	1		EA	5 1/2"	100.00	100.00
401		1			INSERT FLOAT VALVE W/FILUP	1		EA		125.00	125.00
410		1			TOP PLUG	1		EA		50.00	50.00
402		1			CONDUITS	6		EA		44.00	264.00
403		1			CEMENT BASKETS	2		EA		125.00	250.00

LEGAL TERMS: Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, **PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY** provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

X *[Signature]*
 DATE SIGNED: **4-30-03** TIME SIGNED: **1330**
 A.M. P.M.

REMIT PAYMENT TO:
SWIFT SERVICES, INC.
 P.O. BOX 466
 NESS CITY, KS 67560
 785-798-2300

SURVEY	AGREE	UN-DECIDED	DIS-AGREE	PAGE TOTAL	
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?				#1	2502.00
WE UNDERSTOOD AND MET YOUR NEEDS?				#2	6259.11
OUR SERVICE WAS PERFORMED WITHOUT DELAY?					
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?				TAX	
ARE YOU SATISFIED WITH OUR SERVICE? <input type="checkbox"/> YES <input type="checkbox"/> NO				TOTAL	
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND					

CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES The customer hereby acknowledges receipt of the materials and services listed on this ticket.

SWIFT OPERATOR: *[Signature]* APPROVAL:

Thank You!



PO Box 466
Ness City, KS 67560
Off: 785-798-2300

TICKET CONTINUATION

TICKET No. 5273

CUSTOMER V.J.T. WELL HONEY A-1 DATE 4-2-03 PAGE 2 OF 2

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			TIME	DESCRIPTION	QTY.		U/M		UNIT PRICE	AMOUNT
		LOC	ACCT	DF			QTY.	U/M	QTY.	U/M		
330		1				SWIFT WHITE - ADULT STAGGARD	450	SKS			975	438750
276		1				FLOCCS	113	URS			90	10170
581						SERVICE CHARGE						
583						MILEAGE CHARGE						
						TOTAL WEIGHT						
						LOADED MILES						
						TON MILES						

15-068-22898-22-890-51

CONTINUATION TOTAL 6269.11

15-065-22898-05-00

SWIFT Services, Inc.

JOB LOG

DATE 4-2-03 PAGE NO. 1

CUSTOMER V.I.I. WELL NO. A-1 LEASE HOLIFY JOB TYPE 5/2" LONGSTRAWG TICKET NO. 5373

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	1130							ON LOCATION
	1230							START 5/2" CASING IN WELL
								TD - 3980' 5/2" 14" / FT
								TP - 3985' SIT = 3979'
								CS - 14'
								CENTRALIZERS - 1, 3, 5, 9, 63, 84
								CMT BSKTS - 9, 62
	1630							DROP BALL - BREAK CIRCULATION
	1705							PLUG RH
	1710	6	12		✓		450	PUMP 500 GAL MUD FLUSH
		6	20		✓		450	PUMP KCl FLUSH
	1715	6 1/2	194		✓		250	MIX CEMENT - 350 SKS @ 11.2 PPG
			28		✓			100 SKS @ 14.0 PPG
	1750							WASH OUT PUMP LINES
	1752							RELEASE PLUG
	1755	6 1/2	0		✓		900 ^{MAX}	DEBRACK PLUG
	1810		96.9				1200	PLUG DOWN
	1815						OK	RELEASE PSE - HELD
								CIRCULATED 20 SKS CMT TO BIT
								WASH UP
	1930							JOB COMPLETE

THANK YOU
WAVE, DUSTY