


15-179-20005-00-01

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Sheridan County, Sec. 32 Twp. 8S Rge. 26 (E) (W)
Location as "NE/CNWSW" or footage from lines (E/2 SE/4) 150'E NESE
Lease Owner Petroleum, Inc.
Lease Name Twin Shawnee Disposal (Mickey) Well No. 1
Office Address Box 1447, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Disposal
Date well completed 3-27 19 67
Application for plugging filed 4-3 19 79
Application for plugging approved 4-4 19 79
Plugging commenced 6-4 19 79
Plugging completed 6-4 19 79
Reason for abandonment of well or producing formation ceased to accept water

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3930 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Cedar Hills	Water	1785'	1925'	8 5/8	243	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.


Halliburton Services pumped 40 sacks 50/50 pozmix cement, 6% gel. Max. pressure 500#, cement held.

RECEIVED
STATE CORPORATION COMMISSION
JUN 11 1979
6-11-1979
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services
Address Oberlin, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Terry Naylor (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) Terry Naylor

(Address)

Subscribed and sworn to before me this 8th day of June, 1979
Richard H. Dumlaker
Notary Public.

My commission expires May 28, 1981

WELL LOG

Petroleum, Inc.
Sth Floor R.H. Garvey Building
Wichita, Kansas 67200

MICKY #1
Approx. NE SE Sec. 32-8S-26W
Sheridan County, Kansas

Contractor: Chief Drilling Co., Inc. Commenced: 3-17-67
Completed: 3-27-67

Casing Record: 8-5/8" set @ 250' w/200 sacks GL-3 cement.
4-1/2" set @ 3929' w/175 sacks 50-50 Pozmix Salt
Saturated cement.
2-3/8" tubing set @ 2126' w/800 cubic feet 20%
Deicel cement.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Surface Sand & Gravel	0	40	2575 Gr.
Sand & Clay	40	95	2577 D.F.
Shale & Sand Streaks	95	140	2580 K.B.
Shale	140	740	
Shale & Shells	740	1760	
Red Bed	1760	2170	
Anhydrite	2170	2209	
Shale & Shells	2209	2257	
Shale & Lime	2257	3710	
Lime	3710	3930	
Total Depth	3930		

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in approximately the NE SE Section 32-8S-26W, Sheridan County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

V. Richard Hoover
V. Richard Hoover, President

Subscribed and sworn to before me this 29th day of March, 1967.

Carmen R. Cook
Carmen R. Cook, Notary Public

My commission expires: Dec. 12, 1970

