

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-193-20,558 ~~0000~~

LEASE NAME Weyand

WELL NUMBER 5

1650 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 28 TWP. 8 RGE. 32 (E) or (W)

COUNTY Thomas

Date Well Completed 6/10/91

Plugging Commenced 5:00 P.M. 6/10/91

Plugging Completed 7:45 P.M. 6/10/91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR The Dane G. Hansen Trust

ADDRESS P. O. Box 187, Logan, Kansas 67646

PHONE# (013) 689-4816 OPERATORS LICENSE NO. 5285

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on June 10, 1991 (date)

by Ed Schumacher, Hays (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4610

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	372'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

1st Plug @ 2720' w/ 25sx Rat. Hole w/ 15sx
 2nd Plug @ 1910' w/ 100sx Total 190 sx 60/40 Poz, 6% Gel,
 3rd Plug @ 425' w/ 40sx 1/4# Flo-seal per sx.
 4th Plug @ 40' w/ 10sx & wiper plug
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. _____

Address P. O. Box 31, Russell, Kansas 67665

STATE OF Kansas COUNTY OF Phillips, ss.

Dane G. Bales, Manager (Employee of Operator) or ~~Operator~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dane G. Bales

(Address) P. O. Box 187, Logan, Kansas 67646

SUBSCRIBED AND SWORN TO before me this 10 day of July, 19 91

Betty Jane Bittel

My Commission Expires: July 17, 1992

RECEIVED
STATE CORPORATION COMMISSION



7/11/91
11 11 1991
CONSERVATION DIVISION
Wichita, Kansas