

15-193-20207-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202.

Thomas County. Sec. 34 Twp. 8S Rge. 32W ~~EX~~
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines _____
NW NW NW NE

Lease Owner Tanner-Prunt Exploration, Inc.
Lease Name BASTIN Well No. 1


Office Address 1664 Market, Denver, CO. 80202
Character of Well (Completed as Oil, Gas or Dry Hole) _____
Dry Hole

Date Well completed 09-06-19 80
Application for plugging filed 09-06 19 80
Application for plugging approved 09-06 19 80
Plugging commenced 09-06 19 80
Plugging completed 09-06 19 80

Reason for abandonment of well or producing formation _____
No commercial quantity of oil or gas available
If a producing well is abandoned, date of last production _____
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4730'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

T.D. 4730'
Set 1st plug @ 1600' with 70 sx.
2nd plug @ 360' with 20 sx.,
3rd plug @ 40' solid bridge with 10 sx.
Rathole with 5 sx., 50/50 posmix, 6% gel

Plug was down @ 1:30 a.m. 09-06-80.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of September, 19 80

My commission expires 08-18-84

Jeanette A. Metheny
Notary Public.



RECEIVED
STATE CORPORATION COMMISSION
SEP 11 1980
CONSERVATION DIVISION
Wichita, Kansas
9-11-80

CONTRACTOR'S WELL LOG

15-193-20207-00-00

OPERATOR: Tanner-Pruit Exploration, Inc.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: BASTIN #1
 LOCATION: NW NW NW NE, Section 34-8S-32W
 Thomas County, Kansas
 SPUD DATE: 08-28-80
 COMPLETION DATE: 09-06-80

0	53	Surface Clay
53	367	Clay, Sand & Shale
367	470	Shale
470	2174	Shale & Sand
2174	2343	Shale
2343	2697	Bentonite Shale & Sand
2697	2724	Anhydrite
2724	2990	Shale & Sand
2990	3632	Shale
3632	4082	Shale & Lime
4082	4152	Lime & Shale
4152	4209	Shale & Lime
4209	4730	Lime & Shale
	4730	Rotary Total Depth

Spud hole @ 2:30 p.m. 08-28-80. Drilled 367' of a 12-1/4" hole. Ran 9 joints of an 8-5/8" 20# casing (tally 358.40'). Set @ 366'. Cemented with 270 sx. of 60/40 posmix, 3% c.c., 2% gel. Cement by Sun Cementing. Cement did circulate. Plug was down @ 8:30 p.m. 08-29-80.

T.D. 4730'. Set 1st plug @ 1700' with 70 sx., 2nd plug @ 360' with 20 sx., 3rd plug @ 40' solid bridge with 10 sx. Rathole with 5 sx. 50/50 posmix, 6% gel. Cement by Sun Cementing. Plug was down @ 1:30 a.m. 09-06-80.

SAMPLE TOPS:

Anhydrite 2697'
 B/Anhydrite 2724'

RECEIVED
 STATE CORPORATION COMMISSION

SEP 11 1980

CONSERVATION DIVISION
 Wichita, Kansas

9-11-80


STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the BASTIN #1, NW NW NW NE, Section 34-8S-32W, Thomas County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Asst. Sec.-Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 10th day of September, 1980.



Jeannette A. Metheny
 Jeannette A. Metheny, Notary Public