

LEASE NAME Bremenkamp Farms "A"

WELL NUMBER 1

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

330 Ft. from S Section Line

1,980 Ft. from E Section Line

SEC. 14 TWP. 8 RGE. 33 (E) or (W)

COUNTY Thomas

LEASE OPERATOR Anderson Energy, Inc.

ADDRESS 1305 E. Waterman, Suite A, Wichita, KS. 67211

PHONE (316) 265-7929 OPERATORS LICENSE NO. 6484

Date Well Completed 8-4-99

Character of Well D & A

Plugging Commenced 8-4-99

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-4-99

The plugging proposal was approved on 8-4-99 (date)

by Richard Williams (KCC District Agent's Name)

Is ACO-1 filed? No If not, is well log attached? 4,700'

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	302'	Cmtd. w/200 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set:
Spot 25 sax cement @2,732'; push bridge plug to 1,810', pump 100 sax cement on plug thru drill pipe; push bridge plug to 325', pump 40 sax cement on plug thru drill pipe; push wiper plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

Name of Plugging Contractor Shields Drilling Co.

RECEIVED
 STATE CORPORATION COMMISSION
 License No. 51840N

Address PO Box 709, Russell, Kansas 67665

AUG 11 1999

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anderson Energy, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss. Wichita, Kansas

Jack P. Beeman (Employee of Contractor or Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Jack P. Beeman, Inc - Treas

(Address) PO Box 709, Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 10th day of August, 19 99

Richard Phillips
 Notary Public

My Commission Expires:

