

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-193-20,186-00-01

LEASE NAME Vacin Farms

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER 1

3960 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 25 TWP. 8S RGE. 33W (X) or (W)

COUNTY Thomas

Date Well Completed 7/16/86

Plugging Commenced 10/14/86

Plugging Completed 10/14/86

LEASE OPERATOR Jay Boy Oil, Inc.

ADDRESS 8400 Killarney, Wichita, KS. 67206

PHONE#(316) 263-5781 OPERATORS LICENSE NO. 4569

Character of Well Abandoned Oil Well

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? District #1

Is ACO-1 filed? Yes If not, is well log attached? Previously Provided

Producing Formation\*Cherokee Sand Depth to Top 4716' Bottom 4720' T.D. 4803'  
 \*Never Produced

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
--	--	GL	610'	8 5/8"	610'	0
--	--	GL	4799	4 1/2"	4799'	1760
Cherokee Sand	Tight	4716	20	--	--	--

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Sand from 4762' (PBD) to 4660' (across perfs 4716'-20'). 4 sx Common Cmt on Sand w/bailer. Shot off casing. Pulled 1760'. Pump down casing w/10 Bbl Allied Econolite 65/35 poz 10% gel 2% Dical followed by 180 sx cement and 1 sk hulls. Ttl cement = 200 sx. Pressured to 250#/shut in.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Poe Well Service License No. 6779

Address Box 115, Oberlin, KS. 67749

STATE OF Kansas COUNTY OF Sedgwick, ss.

C.K. Morrison

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C.K. Morrison

(Address) C.K. Morrison, Operations Manager  
 8400 Killarney, Wichita, KS. 67206

**BETTY B. HERRING**  
 NOTARY PUBLIC  
 STATE OF KANSAS  
 My Appt. Exp. 10-07-89

RECEIVED  
 SWORN TO before me this 4th day of December, 1986

STATE CORPORATION COMMISSION  
Betty B. Herring  
 Notary Public

My Commission Expires DEC 5 1986 10-07-89

CONSERVATION DIVISION  
 Wichita, Kansas

125-86

Form CP-4  
 Revised 07-86