

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 193-20,403-00-00
LEASE NAME H & H Farms Inc.

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

330' Ft. from S Section Line

2130' Ft. from E Section Line

SEC. 34 TWP. 8 RGE. 33 (E) or (W)

COUNTY Sedgwick

LEASE OPERATOR Jay Boy Oil, Inc.

ADDRESS 8400 Killarney, Wichita, KS. 67206

PHONE# (316) 263-5781 OPERATORS LICENSE NO. 4569

Date Well Completed 7-16-86

Character of Well D&A

Plugging Commenced 10-14-86

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-14-86

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Carl Goodrow Dist #6

Is ACO-1 filed? Yes If not, is well log attached? Previously provided

Producing Formation *Mississippian Depth to Top 4930' KB Bottom 4935' KB, D. 5720' KB
Never Produced

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		7'	261'	8 5/8" 23#	254'	0
		5'	505'	4 1/2" 10 1/2#	5041'	860'
Mississippian	Dry	4930'	35'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sand from 5028 to 4880' (across perfs 4930-35'); 4 sx common cmt on top. Shot csg 2x; pulled 860'. Hook on to 8 5/8" csg. Pump 20 sx cement, 5 sx hulls, followed by 180 sx cmt w/max press= 400 psi. SI w/400#. Total cement was 200 sx Allied Econolite 65/35 Poz 10% Gel 2% dicel.

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Poe Well Service License No. 6779

Address Box 115, Oberlin, KS. 67749

STATE OF Kansas COUNTY OF Sedgwick, ss.

C.K. Morrison (Employee of Operator) ~~XXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C.K. Morrison
C.K. Morrison, Operations Manager
(Address) 8400 Killarney, Wichita, KS.



AND SWORN TO before me this 5th day of December, 1986

Betty B. Herring
Notary Public

My Commission Expires: October 7, 1989

DEC - 5 1986

CONSERVATION DIVISION
Wichita, Kansas

12-5-86