

15-193-20047-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Thomas County. Sec. 16 Twp. 8 Rge. 34 (E) (W)
Location as "NE/CNW/SW" or footage from lines C NW SW
Lease Owner Chief Drilling Co., Inc. & Bill J. Porter
Lease Name Schielke Well No. 1
Office Address 905 Century Plaza, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1/10/74 19
Application for plugging filed 1/9/74 19
Application for plugging approved 1/9/74 19
Plugging commenced 1/10/74 19
Plugging completed 1/10/74 19
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4817 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	341'	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged through drill pipe @ 1925' w/110 cubic feet cement.
Plugged through drill pipe @ 370' w/30 cubic feet cement.
Plugged through drill pipe @ 40 w/10 cubic feet cement.

RECEIVED
STATE CORPORATION COMMISSION
JAN 15 1974
CONSERVATION DIVISION
Wichita, Kansas

1-15-74

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.
Address Suite 905 Century Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. Jim Robinson (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson
905 Century Plaza, Wichita, Kansas 67202 (Address)

Subscribed and sworn to before me this 14th day of January, 19 74

My commission expires August 5, 1975
Virginia S. Fabian
Virginia S. Fabian, Notary Public.



15-193-20047-00-00

WELL LOG

CHIEF DRILLING CO., INC. &
BILL J. PORTER
Suite 905 Century Plaza
Wichita, Kansas 67202

SCHIELKE #1
C NW SW Sec. 16-8-34W
Thomas County, Kansas

CONTRACTOR: Chief Drilling Co., Inc.
CASING RECORD: Set 341' of 8 5/8" w/225 sacks
common quick set cement

COMMENCED: 12/18/73
COMPLETED: 1/10/74

RECEIVED
STATE CORPORATION COMMISSION

JAN 16 1974

CONSERVATION DIVISION
Wichita, Kansas

1-16-74

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Surface Hole	0	252
Shale	252	700
Shale & Sand	700	1752
Shale	1752	2078
Shale & Shells	2078	2332
Shale & Sand	2332	2565
Shale	2565	2777
Shale & Shells	2777	2798
Anhydrite	2798	2831
Shale & Shells	2831	2920
Shale	2920	2996
Shale & Lime	2996	3387
Lime & Shale	3387	3625
Lime	3625	4817
R.T.D.	4817	

ELEVATION

3256 Gr.
3258 D.F.
3261 K.B.

ELECTRIC LOG TOPS

Anhydrite	2794 +	467
Base Anhy.	2824 +	437
Elmont	3816 -	555
Howard	3843 -	582
Topeka	3892 -	631
Heebner	4082 -	821
Toronto	4108 -	847
Lansing	4126 -	1125
B.K.C.	4386 -	1148
Pawnee	4509 -	1149
Ft. Scott	4568 -	1307
Cherokee	4600 -	1339
Mississippi	4708 -	1447
Miss. Dolomite	4748 -	1487
L.T.D.	4817 -	1556

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:


I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C NW SW of Section 16-8-34W, Thomas County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Jim Robinson

Jim Robinson, Vice President

Subscribed and sworn to before me this 15th day of January, 1974.



Virginia S. Fabian

Virginia S. Fabian, Notary Public