

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20859-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 4-5S-32W
990 feet from S Section Line, 330 feet from W Section Line
Lease Name: DAN-DIRKS "A" Well #: 1-4
County: RAWLINS Total Vertical Depth: 4525 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E CENTRAL STE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	220		

147.06

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/24/2008 12:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: KEITH VANPELT Company: MURFIN DRILLING CO., INC. Phone: (785) 443-1857

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: NONE
Date/Time Plugging Completed: 04/24/2008 1:45 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st. Plug at 2637' w/25 sxs.
2nd. Plug at 1766' w/100 sxs.
3rd. Plug at 270' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

INVOICED
DATE 5-13-08
INV. NO. 2008061713

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 02 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Richard Williams

(TECHNICIAN)

CM

Form CP-2/3

APR 28 2008

AW