

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-205-27325-00-00  
Spot: NESWNWSE Sec/Twnshp/Rge: 7-27S-14E  
3330 feet from N Section Line, 2285 feet from E Section Line  
Lease Name: H. MARR Well #: H.P. 1  
County: WILSON Total Vertical Depth: 1229 feet

Operator License No.: 33718

Op Name: MEARS, JOHN C.

Address: 4100 240TH RD  
CHANUTE, KS 66720

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	133		

39.94

Well Type: OH DH KCC PWT

UIC Docket No:

Date/Time to Plug: 04/16/2008 8:00 AM

Plug Co. License No.: 33749

Plug Co. Name: KEPLEY WELL SERVICE, LLC

Proposal Rcvd. from: MIKE KEPLEY

Company: KEPLEY WELL SERVICE

Phone: (620) 433-7196

Proposed Plugging Method: Gel hole and place cement plugs at TD, 500', and 300' to surface.

Plugging Proposal Received By: ALAN DUNNING

Witness Type: PARTIAL

Date/Time Plugging Completed: 04/16/2008 12:00 PM

KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

A 1" cement string was lowered to TD. A 50' cement plug was placed at TD. The cement string was raised to 500' and 50' cement plug placed here. The cement string was raised to 300' and cement placed from 300' to surface. Gel spacers are between cement plugs. A total of 120 sacks of portland cement were used to plug well.

**INVOICED**

DATE 5-13-08  
INV. NO. 2008061714

RECEIVED  
KCC DISTRICT #3

APR 21 2008 AD

CHANUTE, KS

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 02 2008

CONSERVATION DIVISION  
WICHITA, KS

Remarks:

Plugged through: OH

District: 03

Signed

Alan M. Dunning  
(TECHNICIAN)

*PKT*