

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-23474-00-00
Spot: SESWSWSE Sec/Twnshp/Rge: 21-14S-15W
175 feet from S Section Line, 1910 feet from E Section Line
Lease Name: HOUGH-MUDD Well #: 1
County: RUSSELL Total Vertical Depth: 3325 feet

Operator License No.: 6627
Op Name: PROSPECT OIL & GAS CORP
Address: PO BOX 837
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3318		150 SX CMT.
SURF	8.625	221		160 SX CMT.

108.06

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/29/2008 10:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICH MCINTYRE Company: PROSPECT OIL & GAS CORP. Phone: (620) 727-3410

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE
Date/Time Plugging Completed: 04/29/2008 2:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Sanded to 3030' and dumped 5 sxs cement.
Cut off casing at 2470'.
Pulled to 1600' - pumped 100 sxs 60/40 pozmix - 4% gel with 300# hulls.
Pulled to 850' - pumped 25 sxs 60/40 pozmix - 4% gel with 100# hulls.
Pulled to 450' - pumped 30 sxs 60/40 pozmix - 4% gel with 100# hulls.
Pulled to 250' - pumped 70 sxs 60/40 pozmix - 4% gel - cement circulated.

Perfs:

Top	Bot	Thru	Comments
3082	3093		

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 02 2008
CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 5-13-08
INV. NO. 2008061720

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Case Morris
(TECHNICIAN)

APR 30 2008

AMT