

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25165-00-00
Spot: SESWNW Sec/Twnshp/Rge: 14-17S-13W
2310 feet from N Section Line, 1287 feet from W Section Line
Lease Name: REXROAT Well #: 3
County: BARTON Total Vertical Depth: 3430 feet

Operator License No.: 33699
Op Name: T-N-T ENGINEERING, INC.
Address: 3711 MAPLEWOOD STE 201
WICHITA FALLS, TX 76308

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF | 8.625 | 760 | | |

111.48

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/21/2008 12:00 PM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered 150 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE WitnessType: NONE
Date/Time Plugging Completed: 04/21/2008 3:00 PM KCC Agent: BRUCE BASYE

Actual Plugging Report:

1st. Plug at 3300' w/25 sxs.
2nd. Plug at 810' w/40 sxs.
3rd. Plug at 344' w/50 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

INVOICED
DATE S-13-08
INV. NO 2008061726

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 06 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed


(TECHNICIAN)

CM

PKT

Form CP-2/3

MAY 01 2008